

SUMMARY OF QUANTITIES

URBAN

901.FED/101.STATE

901/6.7/33/

Fed./State/City

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0021 SAFETY	0021 SIGNAL AT THORNTON RD	0021 SIGNAL AT 138th ST	0021 SIGNAL AT BROADWAY ST
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	28	28			
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	84	84			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	364	364			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	402	402			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22.786	22.786			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1190	1190			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	389	389			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	386	386			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	319	319			
* 78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS	SQ FT	36	36			
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	3317	3317			
* 78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	FOOT	114	114			
* 78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"	FOOT	314	314			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	235	235			
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	235	235			
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	9	9			
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	25	25			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	14	14			
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1		
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	609		609		
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	149		53	65	31
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	167		102	12	53
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	626		368		258
* 81400100	HANDHOLE	EACH	4		4		
* 81400200	HEAVY-DUTY HANDHOLE	EACH	5		5		
* 81400300	DOUBLE HANDHOLE	EACH	2		1		1
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1	
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		1		1
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4,772		2,240	612	1,920
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,788		1,694	94	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2,479		1,659		820
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	46		46		
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,039		527	101	411
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	7		1	3	3
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		1	1	
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1		1		
* 87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1				1
* 87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	2				2
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1				1
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1		1		
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1		
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2		1	1	
* 87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1		1		
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	32		12	8	12
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8		4		4
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	91		37	14	40
* 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21		21		
* 87900200	DRILL EXISTING HANDHOLE	EACH	17			3	14
* 88000105	FLASHING BEACON INSTALLATION	EACH	2	2			
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	17		5	4	8

\* DENOTES SPECIALTY ITEM

FILE NAME =  
#FILE#

USER NAME = .USER  
DESIGNED - EF  
DRAWN - EF  
PLOT SCALE = 50' / IN.  
PLOT DATE = 12/28/2011

REVISOR - EF  
CHECKED - RS  
DATE - 12-28-2011

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ASH AND AVE. (THORNTON RD. - BROADWAY ST.)  
SUMMARY OF QUANTITIES

SCALE: 1"=50'

SHEET 3 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2857	2011-054-I	COOK	81	5
			CONTRACT NO. 60P64	
ILLINOIS FED. AID PROJECT				