



SIDEWALK REMOVAL AND REPLACEMENT (TYPICAL ALL 4 CORNERS 11'-0" x 5'-0")

**PLAN**

**NOTES:**

- DRAINS TO BE CLEANED COST TO BE INCLUDED STRUCTURAL REPAIR OF CONCRETE  $\leq 5''$
- REMOVAL OF EXISTING SIDEWALK INCLUDED IN THE COST OF PCC SIDEWALK 5 INCH

**BILL OF MATERIALS**

ITEM	UNIT	QUANTITY
STRUCTURAL REPAIR OF CONCRETE $\leq 5''$	SQ.FT.	75
PCC SIDEWALK 5 INCH	SQ.FT.	220

**LEGEND:**

- STRUCTURAL REPAIR OF CONCRETE  $\leq 5''$
- PCC SIDEWALK 5''