

# SUMMARY OF QUANTITIES

				90% I. FED. / 5% STATE / 5% ST. CHARLES	90% I. FED. / 10% STATE / 0% ST. CHARLES	90% I. FED. / 10% STATE / 0% ST. CHARLES	90% I. FED. / 10% STATE / 0% ST. CHARLES	90% I. FED. / 10% STATE / 0% ST. CHARLES	90% I. FED. / 10% STATE / 0% ST. CHARLES	90% I. FED. / 10% STATE / 0% ST. CHARLES
				IL 64 @	IL 64 @	IL 64 @	IL 64 @	IL 64 @	IL 64 @	IL 64 @
				7TH STREET	3RD STREET	2ND STREET	1ST STREET	1ST AVENUE	5TH AVENUE	7TH AVENUE
URBAN										
LOCATION OF WORK										
CONSTRUCTION CODE				0021	0021	0021	0021	0021	0021	0021
SUMMARY OF QUANTITIES										
CODE NO.	ITEM	UNIT	GRAND TOTAL							
67100100	MOBILIZATION	LSUM	1.0	0.142	0.143	0.143	0.143	0.143	0.143	0.143
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1.0	0.142	0.143	0.143	0.143	0.143	0.143	0.143
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1.0	0.142	0.143	0.143	0.143	0.143	0.143	0.143
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LSUM	1.0	0.14	0.143	0.143	0.143	0.143	0.143	0.143
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	7.0	1	1	1	1	1	1	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	137.0							137
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	144.0							144
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	215.0				215			
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	9.0					6	3	
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	8.0		2		3	2		1
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	9.0		2			2	3	2
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	7.0					2	5	
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1.0						1	
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1.0							1
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	10.0	6			2		2	
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	21.0	1	4	4	1	4	3	4
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	16.0					8	8	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	31.0	7	4	4	3	4	5	4
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	7.0	1	1	1	1	1	1	1
X862.0200	UNINTERRUPTABLE POWER SUPPLY SPECIAL	EACH	6.0	1	1	1	1	1	1	
X8950093	RELOCATE EXISTING ELECTRIC SERVICE METER	EACH	1.0				1			