



THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

- 1 EACH SIGNAL HEAD, 1-SECTION

NOTE: TWO SEPARATE SERVICE INSTALLATIONS

| I.D.O.T. TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS | | | | | TOTAL WATTAGE |
|----------------------------------------------------------------------------|-----------|---------|--------|-------------|------------------|
| TYPE | NO. LAMPS | WATTAGE | | % OPERATION | |
| | | INCAND. | L.E.D. | | |
| SIGNAL (RED) | 4 | 135 | 17 | 0.50 | 34.0 |
| SIGNAL (YELLOW) | 2 | 135 | 25 | 0.25 | 12.5 |
| SIGNAL (GREEN) | - | 135 | 15 | 0.25 | - |
| ARROW | - | 135 | 12 | 0.10 | - |
| PED. SIGNAL | - | 90 | 25 | 1.00 | - |
| CONTROLLER | 1 | - | 100 | 1.00 | 100.0 |
| LUMINAIRE | - | - | 250 | 0.50 | - |
| L.E.D. ST. NAME SIGN | - | - | 64 | 0.50 | - |
| VIDEO SYSTEM | - | - | 150 | 1.00 | - |
| BATTERY BACKUP | - | - | 25 | 1.00 | - |
| ILLUMINATED SIGN | - | - | 25 | 0.05 | - |
| TOTAL = | | | | | 146.5 |

ENERGY COSTS - BILLED TO: ILLINOIS DEPT. OF TRANS.
 (ADDRESS) 201 W. CENTER COURT
 (ADDRESS) SCHAUMBURG, IL 60196
 ENERGY SUPPLY - CONTACT: _____
 PHONE: _____
 COMPANY: _____

CABLE PLAN

SCHEDULE OF QUANTITIES
 ILL RTE 47 AT BURLINGTON ROAD - FLASHING BEACONS

| NO. | QUANT. | UNIT | |
|-----|--------|------|------------------------------------------------------|
| 1. | 1 | EACH | MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION |
| 2. | 1 | EACH | SIGNAL HEAD, LED, 1-FACE, 1-SECTION, BRACKET MOUNTED |
| 3. | 1 | EACH | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT |