

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY RE- CONSTRUCTION	RETAINING WALLS	LANDSCAPING ITEMS	TRAFFIC SIGNALS 95TH ST. @ 104TH AVE./ FLAVIN RD.	100% COST TO NORTH PALOS FIRE PROTECTION DISTRICT	CODE NO	ITEM	UNIT		ROADWAY RE- CONSTRUCTION	RETAINING WALLS	LANDSCAPING ITEMS	TRAFFIC SIGNALS 95TH ST. @ 104TH AVE./ FLAVIN RD.	100% COST TO NORTH PALOS FIRE PROTECTION DISTRICT
			0004	0040	0004	0021	0021				0004	0040	0004	0021	0021		
*20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	63		63			54214527	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 42"	EACH	1	1					
*20101000	TEMPORARY FENCE	FOOT	1531		1531			54247130	GRATING FOR CONCRETE FLARED END SECTIONS, 24"	EACH	2	2					
*20101100	TREE TRUNK PROTECTION	EACH	7		7			54248170	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 42"	EACH	1	1					
*20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5		5			542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	120	120					
*20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5		5			542A5497	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	165	165					
20200100	EARTH EXCAVATION	CU YD	10644	10644				55101200	STORM SEWER REMOVAL 24"	FOOT	244	244					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	501	501				59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	53	53					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	61	61				60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	10	10					
*20800150	TRENCH BACKFILL	CU YD	259	259				60100080	FRENCH DRAINS	CU YD	6	6					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	161	161				60107600	PIPE UNDERDRAINS 4"	FOOT	678	678					
*21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	6912		6912			*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1182	1182					
*21101815	COMPOST FURNISH AND PLACE, 4"	SO YD	7069		7069			*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3					
21400100	GRADING AND SHAPING DITCHES	FOOT	2600	2600				63200310	GUARDRAIL REMOVAL	FOOT	255	255					
*25000210	SEEDING, CLASS 2A	ACRE	2		2			*66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	188	188					
*25000310	SEEDING, CLASS 4	ACRE	1		1			*66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180	180				*66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1					
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180	180				67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180	180				67100100	MOBILIZATION	L SUM	1	1					
25100630	EROSION CONTROL BLANKET	SO YD	12985	12985				70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4					
28000305	TEMPORARY DITCH CHECKS	FOOT	243	243				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,652	17,652					
28000400	PERIMETER EROSION BARRIER	FOOT	4944	4944				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	100	100					
28000500	INLET AND PIPE PROTECTION	EACH	6	6				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	6,084	6,084					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	360	360				70400100	TEMPORARY CONCRETE BARRIER	FOOT	1679	1679					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	41	41				70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1700	1700					
40701866	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/4"	SO YD	14000	14000				*72000100	SIGN PANEL - TYPE 1	SO FT	39			39			
44000100	PAVEMENT REMOVAL	SO YD	27,629	27,629				*72000200	SIGN PANEL - TYPE 2	SO FT	27.5			27.5			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	427	427				*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	365	365					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	246	246				*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12806	12806					
48203034	HOT-MIX ASPHALT SHOULDERS, 9 1/4"	SO YD	3941	3941				*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1094	1094					
50300225	CONCRETE STRUCTURES	CU YD	68.7	27.9	40.8			*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	831	831					
50500505	STUD SHEAR CONNECTORS	EACH	118		118												
50800105	REINFORCEMENT BARS	POUND	2810	2810													
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3900	300	3600												
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	EACH	2	2													

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES 95th STREET @ 104th AVENUE / FLAVIN ROAD				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\paw\work\paw\104th\steeppc\015995\PI44499-Dist\grd\g		DRAWN -	REVISED -									1566	29R-N-1	COOK	120	4
PLOT SCALE = 50,0000' / 1"		CHECKED -	REVISED -									CONTRACT NO. 62377				
PLOT DATE = 12/15/2011		DATE -	REVISED -													
				SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								