

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	PAY ITEM	UNIT	TOTAL	0021	0042
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5	
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	38	38	
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	38	38	
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	38	38	
20101700	SUPPLEMENTAL WATERING	UNIT	27	27	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	2,994	2,994	
25200110	SODDING, SALT TOLERANT	SO YD	2,994	2,994	
● 28000510	INLET FILTERS	EACH	100	100	
● 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1,800	1,800	
● 42400800	DETECTABLE WARNINGS	SO FT	240	240	
● 44000600	SIDEWALK REMOVAL	SO FT	1,800	1,800	
6/100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION,STANDARD 701606	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION,STANDARD 701602	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION,STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION,STANDARD 701801	L SUM	1	1	
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	3	
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	70	70	
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	3,632	3,632	
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	221	221	
81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	26,937	26,937	
81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	135	135	
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	1	1	
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	1	1	
82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VCLT, 200AMP	EACH	3	3	
83001300	LIGHT POLE, ALUMINUM, 35 FT. M.H., 8 FT. DAVIT ARM	EACH	83	83	
83001400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. DAVIT ARM	EACH	63	63	
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H.,15 FT. MAST ARM	EACH	2	2	
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	76	76	
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	148	148	
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	8	8	
84200804	REMOVAL OF POLE FOUNDATION	EACH	8	8	
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	592	592	
X8210157	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT (SPECIAL)	EACH	83	83	
X8210161	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT (SPECIAL)	EACH	63	63	
X8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	84	84	
X8360345	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8 5/8" X 7'	EACH	140	140	
X8360360	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 10" X 8'	EACH	2	2	
Z0076600	TRAINEES	HOUR	500		500

● INDICATES SPECIALTY ITEMS

FILE NAME = q:\CH09\8132\Road\500.dgn	USER NAME = ajpondexter	DESIGNED - KB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE. 2578	SECTION 10-00059-00-LT	COUNTY COOK	TOTAL SHEETS 21	SHEET NO. 3	
PLOT SCALE = #SCALE#	CHECKED - SRF	REVISED -	SCALE: NTS			SHEET NO. 3 OF 21 SHEETS	STA. TO STA.	2585	JOB NO. C-91-460-10	CONTRACT NO. 63530	
PLOT DATE = 12/28/2011	DATE - 11/04/2011	REVISED -				FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT			