F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
856	01-00170-26-TL	WILL	171	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO: 63570				

WEBER ROAD AT RENWICK ROAD INTERSECTION IMPROVEMENT

SP	SI	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
						STA 0003	STP 0003	STA TRAFFIC SIGNALS 0021	TRAINEES 0042
	+	88600100	DETECTOR LOOP, TYPE I	FOOT	101			101	
	+	88600700	PREFORMED DETECTOR LOOP	FOOT	2,161			2,161	
*	+	88700200	LIGHT DETECTOR	EACH	5			5	
*	+	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1	
*	+	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2			2	
*	+	89500300	RELOCATE EXISTING ILLUMINATED SIGN	EACH	4			4	
*	+	89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	1			1	
*	+	89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1			1	
*	+	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	12,109			12,109	
*	+	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2			2	
*	+	89502380	REMOVE EXISTING HANDHOLE	EACH	8			8	
*	+	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	14		5	9	
*		X0322936	REMOVE EXISTING FLARED END SECTION	EACH	19		19		
*		X2110100	TOPSOIL FURNISH AND PLACE, SPECIAL	CU YD	5,564		5,564		
*		X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	19		19		
*		X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4		4		
*		X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	1,800		1,800		
*		X6020298	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	9		9		
*		X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1		
*	+	X8570225	FULL-ACTUATED CONTROLLER AND CABINET, TYPE IV, SPECIAL	EACH	2			2	
*	+	X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3C, TWISTED, SHIELDED	FOOT	1,633			1,633	
*		Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	81,745	81,428	317		
		Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1		
*	+	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	14		14		
*	+	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	2			2	
*		Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3,604	3,604			
*		Z0062456	TEMPORARY PAVEMENT	SQ YD	8,643		8,643		
*	+	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2			2	
*		Z0076600	TRAINEES	HOUR	2,000				2,000

* SPECIAL PROVISION, PLAN NOTE, OR DETAIL HAS BEEN PROVIDED.

\+ SPECIALITY ITEM.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WEBER ROAD AND RENWICK ROAD
SUMMARY OF QUANTITIES

SCALE: DRAWN BY CJO

DATE APRIL, 2011 CHECKED BY MFB

11/1/2011
P:\79766\cadd\drawings\008SumQuant.dgn