F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
856	01-00170-26-TL	WILL	171	75
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO: 63570				

WEBER ROAD DRAINAGE PIPE SCHEDULE - SOUTH LEG

PIPE NO.	PIPE PAY ITEM NAME	FROM STRUCTURE	FROM STATION	TO STRUCTURE	TO STATION	TYPE	DIAMETER (INCH)	LENGTH (FT)	TRENCH BACKFILL (CU YD)	PAY ITEM NO.
P 100	STORM SEWERS, CLASS A, TYPE 2 12"	S 100	32+00.00	S 101	32+00.00	2	12	69	16.1	550A0340
P 101	STORM SEWERS, CLASS A, TYPE 2 12"	S 101	32+00.00	S 102	31+97.00	2	12	10	0.0	550A0340
P 102	STORM SEWERS, CLASS A, TYPE 1 54"	S 102	31+97.00	S 103	31+60.00	1	54	41	12.9	550A0200
P 103	STORM SEWERS, CLASS A, TYPE 1 54"	S 103	31+60.00	S 104	31+50.00	1	54	10	6.1	550A0200
P 105	STORM SEWERS, CLASS A, TYPE 1 12"	S 105	35+80.00	S 106	35+41.83	1	12	38	2.6	550A0050
P 106	STORM SEWERS, CLASS A, TYPE 1 15"	S 106	35+41.83	S 107	35+41.83	1	15	86	8.1	550A0070
P 106A	STORM SEWERS, CLASS A, TYPE 1 12"	S 106A	35+30.00	S 106	35+41.83	1	12	12	0.9	550A0050
P 107	STORM SEWERS, CLASS A, TYPE 2 12"	S 107	35+41.83	S 109	35+41.83	2	15	9	0.0	550A0340
P 108	STORM SEWERS, CLASS A, TYPE 1 15"	S 108	35+50.00	S 107	35+41.83	1	12	10	0.9	550A0070
P 109	STORM SEWERS, CLASS A, TYPE 1 54"	S 109	35+41.83	S 102	31+97.00	1	54	345	0.0	550A0200
P 110	STORM SEWERS, CLASS A, TYPE 2 12"	S 110	36+70.00	S 111	36+70.00	2	12	90	19.0	550A0340
P 111	STORM SEWERS, CLASS A, TYPE 2 15"	S 111	36+70.00	S 112	36+70.00	2	15	8	0.0	550A0360
P 112	STORM SEWERS, CLASS A, TYPE 2 54"	S 112	36+70.00	S 109	35+41.83	2	54	128	0.0	550A0490
P 113	STORM SEWERS, CLASS A, TYPE 2 12"	S 113	38+00.00	S 114C	38+00.00	2	12	54	23.7	550A0340
P 113A	STORM SEWERS, CLASS A, TYPE 1 12"	S 113A	38+37.00	S 113	38+00.00	1	12	37	4.3	550A0050
P 114A	STORM SEWERS, CLASS A, TYPE 2 12"	S 114A	37+50.00	S 114B	37+50.00	2	12	16	3.9	550A0340
P 114B	STORM SEWERS, CLASS A, TYPE 2 12"	S 114B	37+50.00	S 114C	38+00.00	2	12	50	23.5	550A0340
P 114C	STORM SEWERS, CLASS A, TYPE 2 12"	S 114C	38+00.00	S 114	38+00.00	2	12	39	20.1	550A0340
P 114	STORM SEWERS, CLASS A, TYPE 2 15"	S 114	38+00.00	S 115	38+00.00	2	15	8	0.0	550A0360
P 115	STORM SEWERS, CLASS A, TYPE 2 54"	S 115	38+00.00	S 112	36+70.00	2	54	130	0.0	550A0490
P 116	STORM SEWERS, CLASS A, TYPE 2 12"	S 116	40+31.00	S 117	40+31.00	2	12	50	13.0	550A0340
P 117	STORM SEWERS, CLASS A, TYPE 2 12"	S 117	40+31.00	S 118	40+31.00	2	12	6	3.2	550A0340
P 118	STORM SEWERS, CLASS A, TYPE 2 12"	S 118	40+31.00	S 119	40+31.00	2	12	38	18.7	550A0340
P 119	STORM SEWERS, CLASS A, TYPE 2 12"	S 119	40+31.00	S 120	40+25.00	2	12	10	0.0	550A0340
P 120	STORM SEWERS, CLASS A, TYPE 2 54"	S 120	40+25.00	S 115	38+00.00	2	54	225	153.4	550A0490
P 121	STORM SEWERS, CLASS A, TYPE 2 12"	S 121	41+15.00	S 122	41+15.00	2	12	97	22.1	550A0340
P 121A	STORM SEWERS, CLASS A, TYPE 1 12"	S 121A	41+15.00	S 121	41+15.00	1	12	12	0.0	550A0050
P 122	STORM SEWERS, CLASS A, TYPE 2 15"	S 122	41+15.00	S 123	41+00.00	2	15	18	0.0	550A0360
P 123	STORM SEWERS, CLASS A, TYPE 2 54"	S 123	41+00.00	S 120	40+25.00	2	54	75	0.0	550A0490
P 123A	STORM SEWERS, CLASS A, TYPE 2 12"	S 123A	40+85.00	S 123	41+00.00	2	12	16	0.0	550A0340
P 124	STORM SEWERS, CLASS A, TYPE 2 12"	S 124	42+50.00	S 125	42+50.00	2	12	51	10.5	550A0340
P 125	STORM SEWERS, CLASS A, TYPE 2 12"	S 125	42+50.00	S 126	42+50.00	2	12	13	6.7	550A0340
P 126	STORM SEWERS, CLASS A, TYPE 2 12"	S 126	42+50.00	S 127	42+50.00	2	12	40	19.7	550A0340
P 127	STORM SEWERS, CLASS A, TYPE 2 15"	S 127	42+50.00	S 128	42+50.00	2	15	8	0.0	550A0360
P 128	STORM SEWERS, CLASS A, TYPE 2 54"	S 128	42+50.00	S 123	41+00.00	2	54	150	0.0	550A0490
P 128A	STORM SEWERS, CLASS A, TYPE 1 54"	S 128A	42+65.00	S 128	42+50.00	1	54	15	0.0	550A0200
P 129	STORM SEWERS, CLASS A, TYPE 2 12"	S 129	43+95.00	S 130	43+95.00	2	12	107	22.4	550A0340
P 130	STORM SEWERS, CLASS A, TYPE 2 15"	S 130	43+95.00	S 131	43+95.00	2	15	11	0.0	550A0360
P 131	STORM SEWERS, CLASS A, TYPE 2 54"	S 131	43+95.00	S 128A	42+65.00	2	54	130	0.0	550A0490
P 132	STORM SEWERS, CLASS A, TYPE 2 12"	S 132	45+50.00	S 134	45+50.00	2	12	55	13.7	550A0340
P 134	STORM SEWERS, CLASS A, TYPE 2 12"	S 134	45+50.00	S 135	45+50.00	2	12	52	27.8	550A0340
P 135	STORM SEWERS, CLASS A, TYPE 2 15"	S 135	45+50.00	S 136	45+50.00	2	15	11	0.0	550A0360
P 136	STORM SEWERS, CLASS A, TYPE 2 54"	S 136	45+50.00	S 131	43+95.00	2	54	155	0.0	550A0490
P 136A	STORM SEWERS, CLASS A, TYPE 2 12"	S 136A	45+60.00	S 136	45+50.00	2	12	10	0.0	550A0340
P 137	STORM SEWERS, CLASS A, TYPE 2 12"	S 137	47+10.00	S 138	47+10.00	2	12	44	8.8	550A0340
P 138	STORM SEWERS, CLASS A, TYPE 2 12"	S 138	47+10.00	S 139	47+10.00	2	12	63	32.0	550A0340
P 139	STORM SEWERS, CLASS A, TYPE 2 15"	S 139	47+10.00	S 140	47+10.00	2	15	11	0.0	550A0360
P 140	STORM SEWERS, CLASS A, TYPE 2 48"	S 140	47+10.00	S 136	45+50.00	2	48	160	0.0	550A0480

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WEBER ROAD
DRAINAGE PIPE SCHEDULES

SCALE:
DATE APRIL, 2011

DRAWN BY CJO
CHECKED BY MFB

8/22/2011
P:\79766\cadd\drawings\070dr-Sched.dgn