F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
856	01-00170-26-TL	WILL	171	80
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO: 63570				

DRAINAGE STRUCTURE REMOVAL SCHEDULE

ALIGNMENT	STATION	OFFSET (FT)	STRUCTURE TYPE MH	CB	INLET	FES	TRENCH BACKFILL (CU YD)	PAY ITEM NO.
WEBER RD.	31+57	32.75' LT			INLET		1.9	60500060
WEBER RD.	31+59	26.50' RT	MH				6.0	60500040
WEBER RD.	31+59	31.50' RT		CB			9.0	60500050
WEBER RD.	35+80	32.50' LT			INLET		2.1	60500060
WEBER RD.	35+82	31.75' RT	MH				6.6	60500040
WEBER RD.	35+83	37.75' RT	MH				4.2	60500040
WEBER RD.	35+87	32.50' RT			INLET		1.0	60500060
WEBER RD.	38+35	32.25' LT			INLET		1.7	60500060
WEBER RD.	38+36	36.75' RT	MH				6.0	60500040
WEBER RD.	38+37	43.75' RT			INLET		1.9	60500060
WEBER RD.	40+30	32.00' RT			INLET		1.5	60500040
WEBER RD.	40+30	44.00' RT			INLET		1.8	60500060
WEBER RD.	41+13	32.50' RT	MH				6.0	60500040
WEBER RD.	41+16	32.25' LT			INLET		2.0	60500060
WEBER RD.	41+17	37.75' RT	MH				4.4	60500040
WEBER RD.	41+19	32.50' RT			INLET		1.6	60500060
WEBER RD.	43+79	32.00' RT	MH				5.4	60500040
WEBER RD.	43+80	32.75' LT			INLET		2.0	60500060
WEBER RD.	43+83	36.50' RT	MH				3.7	60500040
WEBER RD.	43+87	32.00' RT			INLET		1.2	60500060
WEBER RD.	46+39	42.75' RT	MH				5.6	60500040
WEBER RD.	46+49	33.00' RT		CB			5.1	60500050
WEBER RD.	46+51	32.50' LT			INLET		2.0	60500060
WEBER RD.	52+98	32.00' LT			INLET		2.1	60500060
WEBER RD.	52+98	46.00' LT				FES	1.2	X0322936
WEBER RD.	52+98	32.25' RT			INLET		1.1	60500060
WEBER RD.	52+98	45.50' RT				FES	1.0	X0322936
WEBER RD.	55+52	27.50' LT			INLET		1.6	60500060
WEBER RD.	55+52	42.00' LT				FES	1.0	X0322936
WEBER RD.	55+53	27.00' RT			INLET		0.6	60500060
WEBER RD.	55+53	40.00' RT				FES	0.8	X0322936
WEBER RD.	58+13	26.25' LT			INLET		1.4	60500060
WEBER RD.	58+13	39.00' LT				FES	0.8	X0322936
WEBER RD.	58+13	26.00' RT			INLET		1.4	60500060
WEBER RD.	58+13	38.75' RT				FES	0.8	X0322936
WEBER RD.	60+68	26.25' LT			INLET		1.3	60500060
WEBER RD.	60+68	38.75' LT				FES	0.8	X0322936
WEBER RD.	60+68	26.00' RT			INLET		1.7	60500060
WEBER RD.	60+68	39.00' RT				FES	0.9	X0322936
WEBER RD.	63+22	22.25' RT			INLET		1.3	60500060
WEBER RD.	63+22	37.25' RT				FES	0.7	X0322936
WEBER RD.	63+23	26.25' LT			INLET		1.3	60500060
WEBER RD.	63+23	39.25' LT				FES	0.7	X0322936
WEBER RD.	65+33	54.00' RT				FES	0.7	X0322936
WEBER RD.	65+42	42.75' RT		CB			3.4	60500050
WEBER RD.	65+42	54.00' RT		CB			4.4	60500050
WEBER RD.	65+77	37.25' LT		CB			3.5	60500050
WEBER RD.	65+77	54.25' LT				FES	0.9	X0322936
WEBER RD.	65+99	59.50' LT				FES	0.0	X0322936
RENWICK RD.	108+53	39.75' RT		CB			3.7	60500050
RENWICK RD.	108+68	39.00' RT				FES	1.0	X0322936
RENWICK RD.	117+20	41.25' RT	MH				4.6	60500040
RENWICK RD.	117+64	38.75' RT				FES	0.9	X0322936
RENWICK RD.	117+77	50.25' RT			INLET		2.8	60500060
RENWICK RD.	119+12	50.25' RT			INLET		2.1	60500060
RENWICK RD.	119+18	37.50' LT				FES	0.9	X0322936
RENWICK RD.	119+21	40.75' RT				FES	1.2	X0322936
RENWICK RD.	119+23	33.00' RT				FES	1.4	X0322936
RENWICK RD.	124+18	27.50' LT				FES	1.3	X0322936
RENWICK RD.	124+19	44.00' RT	MH				6.9	60500040
RENWICK RD.	125+39	86.50' RT		CB			5.4	60500050
RENWICK RD.	127+97	42.75' RT			INLET		0.0	60500060
		TOTALS	**11**	**7**	**25**	**19**		
			TRENCH BACKFILL SUB-TOTAL:				150.1	

PIPE REMOVAL SCHEDULE

ALIGNMENT	FROM STATION	OFFSET (FT)	TO STATION	OFFSET (FT)	DIAMETER (IN)	LENGTH (FT)	TRENCH BACKFILL (CU YD)	PAY ITEM NO.
WEBER RD.	31+57	32.75' LT	31+59	26.50' RT	12	59	20.4	55100500
WEBER RD.	31+59	31.50' RT	31+59	26.50' RT	12	5	2.5	55100500
WEBER RD.	31+50	27.00' RT	31+59	26.50' RT	24	9	11.8	55100500
WEBER RD.	31+59	26.50' RT	35+83	37.75' RT	24	423	225.1	55101200
WEBER RD.	35+80	42.50' LT	35+80	32.50' LT	6	10	1.3	55100200
WEBER RD.	35+80	32.50' LT	35+82	31.75' RT	12	64	26.5	55100500
WEBER RD.	35+82	31.75' RT	35+83	37.75' RT	12	6	2.2	55100500
WEBER RD.	35+83	37.75' RT	35+87	32.50' RT	12	5	1.1	55100500
WEBER RD.	35+83	37.75' RT	38+36	36.75' RT	18	254	129.3	55100900
WEBER RD.	38+35	46.00' LT	38+35	32.25' LT	6	13	1.8	55100200
WEBER RD.	38+35	32.25' LT	38+36	36.75' RT	12	7	2.3	55100500
WEBER RD.	38+36	36.75' RT	38+37	43.75' RT	12	69	23.8	55100500
WEBER RD.	40+30	32.00' RT	40+30	44.00' RT	12	12	3.0	55100500
WEBER RD.	38+36	36.75' RT	41+13	32.50' RT	18	277	143.6	55100900
WEBER RD.	41+13	32.50' RT	41+16	32.25' RT	12	7	2.6	55100500
WEBER RD.	41+15	61.00' LT	41+15	32.25' LT	6	29	4.5	55100200
WEBER RD.	41+16	32.25' LT	41+17	37.75' RT	12	65	24.8	55100500
WEBER RD.	41+17	37.75' RT	41+19	32.50' RT	12	6	1.7	55100500
WEBER RD.	41+13	32.50' RT	43+79	32.00' RT	18	266	125.5	55100900
WEBER RD.	43+79	32.00' RT	43+80	32.75' LT	12	65	22.7	55100500
WEBER RD.	43+79	32.00' RT	43+83	36.50' RT	12	5	1.1	55100500
WEBER RD.	43+83	36.50' RT	43+87	32.00' RT	12	6	1.3	55100500
WEBER RD.	43+79	32.00' RT	46+39	42.75' RT	12	260	101.6	55100500
WEBER RD.	46+39	42.75' RT	46+49	33.00' RT	12	14	5.5	55100500
WEBER RD.	46+49	33.00' RT	46+51	32.50' LT	12	67	23.1	55100500
WEBER RD.	52+98	32.00' LT	52+98	46.00' LT	12	15	5.1	55100500
WEBER RD.	52+98	32.25' RT	52+98	45.50' RT	12	15	2.6	55100500
WEBER RD.	55+52	27.50' LT	55+53	42.00' LT	12	16	4.0	55100500
WEBER RD.	55+53	27.00' RT	55+53	40.00' RT	12	14	1.2	55100500
WEBER RD.	58+13	26.25' LT	58+13	39.00' LT	12	14	3.2	55100500
WEBER RD.	58+13	26.00' RT	58+13	38.75' RT	12	14	3.1	55100500
WEBER RD.	60+68	26.25' LT	60+69	38.75' LT	12	14	2.9	55100500
WEBER RD.	60+68	26.00' RT	60+68	39.00' RT	12	14	3.8	55100500
WEBER RD.	63+22	22.25' RT	63+22	37.25' RT	12	13	2.5	55100500
WEBER RD.	63+23	26.25' LT	63+23	39.25' LT	12	14	2.8	55100500
WEBER RD.	65+33	54.00' RT	65+42	54.00' RT	15	8	2.4	55100700
WEBER RD.	65+42	42.75' RT	65+42	54.00' RT	15	11	3.0	55100700
WEBER RD.	65+42	54.00' RT	66+12	52.50' RT	15	70	0.0	55100700
WEBER RD.	65+77	37.25' LT	65+77	54.25' LT	15	17	4.7	55100700
WEBER RD.	65+99	59.50' LT	66+32	59.50' LT	15	33	3.4	55100700
RENWICK RD.	108+19	40.00' RT	108+68	39.00' RT	18	49	13.8	55100700
RENWICK RD.	117+14	56.50' RT	117+20	41.25' RT	12	16	3.4	55100500
RENWICK RD.	117+20	41.25' RT	117+64	38.75' RT	15	45	12.5	55100700
RENWICK RD.	117+77	50.25' RT	119+12	50.25' RT	24	135	71.9	55101200
RENWICK RD.	117+77	50.25' RT	117+77	61.50' RT	24	11	7.0	55101200
RENWICK RD.	119+12	50.25' RT	119+21	40.75' RT	24	9	4.1	55101200
RENWICK RD.	125+39	86.50' RT	125+39	99.00' RT	18	12	5.5	55100700
RENWICK RD.	127+97	42.75' RT	127+97	60.00' RT	18	17	0.0	55100700
				TRENCH BACKFILL SUB-TOTAL:			1,072.1	

CULVERT REMOVAL SCHEDULE

ALIGNMENT	FROM STATION	OFFSET (FT)	TO STATION	OFFSET (FT)	CULVERT TYPE	DIAMETER (IN)	LENGTH (FT)	TRENCH BACKFILL (CU YD)	PAY ITEM NO.
WEBER RD.	60+96	42.00' RT	61+30	41.75' RT	CMP	15	34	9.8	50105220
WEBER RD.	62+56	42.00' RT	62+89	42.00' RT	CMP	15	33	4.5	50105220
RENWICK RD.	89+70	35.25' RT	90+16	35.00' RT	CMP	15	46	0.0	50105220
RENWICK RD.	92+16	39.25' RT	92+45	38.75' RT	CMP	15	29	8.2	50105220
RENWICK RD.	92+67	38.75' RT	93+17	39.50' RT	CMP	15	50	11.8	50105220
RENWICK RD.	100+84	48.75' LT	102+06	48.00' LT	CMP	15	122	41.5	50105220
RENWICK RD.	100+83	39.75' RT	102+12	39.75' RT	CMP	15	129	37.1	50105220
RENWICK RD.	106+28	48.00' LT	107+06	69.25' LT	CMP	15	78	28.9	50105220
RENWICK RD.	111+20	50.50' LT	111+80	50.75' LT	CMP	15	60	20.2	50105220
RENWICK RD.	116+76	44.00' LT	117+16	44.00' LT	CMP	12	40	4.8	50105220
RENWICK RD.	118+11	42.75' LT	118+39	43.25' LT	CMP	15	28	4.5	50105220
RENWICK RD.	119+18	37.50' LT	119+23	33.00' RT	CMP	24	84	32.7	50105220
RENWICK RD.	124+19	27.50' LT	124+19	44.00' RT	CMP	18	85	44.1	50105220
RENWICK RD.	124+19	44.00' RT	125+39	86.50' RT	CMP	18	127	13.8	50105220
RENWICK RD.	133+87	34.50' LT	134+24	34.00' LT	CMP	15	37	14.6	50105220
					TRENCH BACKFILL SUB-TOTAL:			276.6	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WEBER ROAD AND RENWICK ROAD
REMOVAL & ADJUSTMENT SCHEDULES

SCALE:
DATE APRIL, 2011

DRAWN BY CJO
CHECKED BY MFB

8/22/2011
P:\79766\cadd\drawings\060d-RemSched.dgn