

SPECIALTY ITEM	SPECIAL PROVISION	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
						0004	0014	0042	
		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1		
		50102400	CONCRETE REMOVAL	CU YD	1.9		1.9		
		50104650	SLOPE WALL REMOVAL	SQ YD	1		1		
		50105220	PIPE CULVERT REMOVAL	FOOT	49	49			
		50300225	CONCRETE STRUCTURES	CU YD	3.9		3.9		
		50300300	PROTECTIVE COAT	SQ YD	426		426		
	*	50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	3780		3780		
		50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2220		2220		
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5910		5910		
*		50901050	STEEL RAILING, TYPE SM	FOOT	271		271		
		51100300	SLOPE WALL 6 INCH	SQ YD	1		1		
		51500100	NAME PLATES	EACH	1		1		
		54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	104	104			
		54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1			
		54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1			
		54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	1	1			
		54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1			
		550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	28	28			
		550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	161	161			
		550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	9	9			
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	32	32			
		550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	42	42			
		59000200	EPOXY CRACK INJECTION	FOOT	99		99		
		60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
		60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2	2			
		60207915	CATCH BASINS, TYPE C, TYPE IIV FRAME AND GRATE	EACH	1	1			
		60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2			
		60236825	INLETS, TYPE A, TYPE IIV FRAME AND GRATE	EACH	1	1			
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	460	460			
*		63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	37.5	37.5			
*		63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	3	3			
*		63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2			

PLOT DATE = 12/21/2011
 FILE NAME = K:\A\102245-000 Projns Street\001\Sheets\Print\999 - 500.dgn
 USER NAME = mrc-tul



DESIGNED - LM	REVISED - _____
CHECKED - GG	REVISED - _____
DRAWN - LM	REVISED - _____
CHECKED - DSB	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SHEET NO. 2 OF 3 SHEETS

F.A.U. RTE. 3895	SECTION 08-15104-01-BR	COUNTY KANE	TOTAL SHEETS 38	SHEET NO. 4
ILLINOIS FED. AID PROJECT CONTRACT NO. 63661				