

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% COUNTY ROADWAY 0004	80% FED 20% STATE BRIDGE 0014
20200100	EARTH EXCAVATION	CU YD	40		40
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10		10
20400800	FURNISHED EXCAVATION	CU YD	175		175
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4,895		4,895
25000210	SEEDING, CLASS 2A	ACRE	0.9		0.9
25000314	SEEDING, CLASS 4B	ACRE	0.2		0.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81		81
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81		81
25100630	EROSION CONTROL BLANKET	SQ YD	4,895		4,895
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,621		1,621
28000315	AGGREGATE DITCH CHECKS	TON	65		65
28000400	PERIMETER EROSION BARRIER	FOOT	1,266		1,266
28000510	INLET FILTERS	EACH	1		1
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2,977	2,765	212
40600300	AGGREGATE (PRIME COAT)	TON	61	56	5
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	45	45	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	505	473	32
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	117		117
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1,459	1,355	104
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	85		85
44000100	PAVEMENT REMOVAL	SQ YD	895		895
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	2,874	2,560	314
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	12,007	11,261	746
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,240		1,240
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	310	310	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	310	310	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	228	228	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	100.0		100.0
50200100	STRUCTURE EXCAVATION	CU YD	115.0		115

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% COUNTY ROADWAY 0004	80% FED 20% STATE BRIDGE 0014
50300225	CONCRETE STRUCTURES	CU YD	169.4		169.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	326.9		326.9
50300260	BRIDGE DECK GROOVING	SQ YD	1,258		1,258
50300300	PROTECTIVE COAT	SQ YD	1,791		1,791
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	9,972		9,972
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	99,750		99,750
50800515	BAR SPLICERS	EACH	388		388
51500100	NAME PLATES	EACH	1		1
59000200	EPOXY CRACK INJECTION	FOOT	33		33
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	87		87
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,240		1,240
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS	FOOT	37.5		37.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2		2
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2		2
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2		2
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	2		2
63200310	GUARDRAIL REMOVAL	FOOT	275		275
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7		7
67100100	MOBILIZATION	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	112		112
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14		14
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,696		1,696
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	73		73
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FT	4,995		4,995
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FT	150		150
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FT	74		74
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	357		357
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,106		2,106
70400100	TEMPORARY CONCRETE BARRIER	FOOT	406		406
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	388		388
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73	

* SPECIALTY ITEMS