


SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% COUNTY ROADWAY 0004	80% FED 20% STATE BRIDGE 0014
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,358	2,805	6,553
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	300	300	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	37	37	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	802		802
* 78100105	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)	EACH	9		9
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16		16
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	33		33
* 78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	2		2
78300100	PAVEMENT MARKING REMOVAL	SQ FT	712		712
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	153	30	123
* 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	125		125
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	173	173	0
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	77		77
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	1,110		1,110
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
* X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	144	30	114
* 89502376	REBUILD EXISTING HANDHOLE	EACH	5		5
Z0005216	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	186		186
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 IN.)	SQ FT	158		158
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 IN.)	SQ FT	5		5
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	209		209
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	1		1
Z0026407	TEMPORARY SHEET PILING	SQ FT	276		276
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1		1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	103		103
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	228		228
Z0062456	TEMPORARY PAVEMENT	SQ YD	895		895
Δ Z0076600	TRAINEES	hour	1,000		1,000
* XX006044	PULL AND REINSTALL FIBER OPTIC CABLE	FOOT	1,620		1,620
XX003338	TEST HOLES	EACH	4		4

Δ 0042

USER NAME = dsypren@lisle	DESIGNED - JAC	REVISED -	 PATRICK ENGINEERING INC. 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	DUPAGE COUNTY DIVISION OF TRANSPORTATION	SUMMARY OF QUANTITIES 75TH STREET OVER EAST BRANCH DUPAGE RIVER		FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT CONFIG = PDF(Greg_Large).plt	DRAWN - JAC	REVISED -			0369	08-00162-03-BR	DUPAGE	58	4			
PLOT SCALE = 1:50	CHECKED - DES	REVISED -			SCALE:		SHEET	* OF *	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
PLOT DATE = 1/6/2012	DATE - 12-19-2011	REVISED -										