CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE HBP/TBP FUNDS 80% FED 20% LOCAL ROADWAY 0004 URBAN	80% FED 20% LOCAL BRIDGE 0011 URBAN	80% FED 20% LOCAL TRAINEES 0042 URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	602	602		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	589	589		
20101000	TEMPORARY FENCE	FOOT	80	80		
20101100	TREE TRUNK PROTECTION	EACH	10	10		
⚠ 20101200	TREE ROOT PRUNING	EACH	23	23		
⚠ 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	13	13		
⚠ 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	10	10		
20200100	EARTH EXCAVATION	CU YD	600	600		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,400	1,400		
20400800	FURNISHED EXCAVATION	CU YD	6,140	6,140		
20800150	TRENCH BACKFILL	CU YD	80	80		
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4,215	4,215		
⚠ 25000210	SEEDING, CLASS 2A	ACRE	.25	.25		
⚠ 25000310	SEEDING, CLASS 4	ACRE	1.25	1.25		
⚠ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	135	135		
⚠ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	135	135		
⚠ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	135	135		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	7,260	7,260		
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	10	10		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	127	127		
28000400	PERIMETER EROSION BARRIER	FOOT	2,016	2,016		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28000510	INLET FILTERS	EACH	2	2		
28001000	AGGREGATE (EROSION CONTROL)	TON	1	1		
28100107	STONE RIPRAP, CLASS A4	SQ YD	516	16	500	
28200200	FILTER FABRIC	SQ YD	516	16	500	

⚠ SPECIALTY ITEMS

FILE NAME = S:\JOL\68828-68991\6842\087\Micros\CADD Sheets\01-63666-sht-SQU.dgn

STRAND ASSOCIATES®
1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = dennisw
PLOT SCALE = 1.0000 ' / IN.
PLOT DATE = 1/8/2021

DESIGNED VLF
DRAWN VJF
CHECKED AJS

REVISED -
REVISED -
REVISED -

MCHENRY COUNTY DIVISION OF TRANSPORTATION
HILL ROAD BRIDGE OVER
NORTH BRANCH NIPPERSINK CREEK

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

TR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
21	08-00356-00-BR	MCHENRY	67	4

CONTRACT NO. 63666

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT