

**SUMMARY OF QUANTITIES
CONSTRUCTION TYPE CODE 0005**

CODE	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	4008
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	672.7
40600895	CONSTRUCTION TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	312.2
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N50	TON	1571.2
S 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	195.6
42400800	DETECTABLE WARNINGS	SQ FT	86
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	16032.5
S 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	317.1
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	87
44000600	SIDEWALK REMOVAL	SQ FT	261.6
S 44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	100
S 44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	100
S 44201879	CLASS D PATCHES, TYPE III 19 INCH	SQ YD	100
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2500
48101200	AGGREGATE SHOULDERS, TYPE B	TON	296.6
S 54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	10
54247090	GRATING FOR FLARED END SECTION 12"	EACH	10
S 550A0050	STORM SEWERS, CLASS A TYPE 1 12"	FOOT	237
55100500	STORM SEWER REMOVAL 12"	FOOT	237
S 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	87
67100100	MOBILIZATION	L SUM	1
S 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
S 70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
S 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
S 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	190
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4'	FOOT	11890
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6'	FOOT	1374
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12'	FOOT	348
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24'	FOOT	94.5
S * 88600600	DETECTOR LOOP REPLACEMENT	FOOT	322
S Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3'	SQ YD	317.1

* = DENOTES SPECIALTY ITEM
S = SPECIAL PROVISION