

PI NO	DESCRIPTION	UNIT	QTY	SPECIAL PROVISION	SPECIALTY ITEM	CONSTRUCTION CODE
60500040	REMOVING MANHOLES	EACH	2			0003
60500050	REMOVING CATCH BASINS	EACH	3			0003
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	350			0003
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	3835			0003
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	8962			0003
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ.FT	11536			0003
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ.FT	512			0003
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24			0003
67100100	MOBILIZATION	L.SUM	1			0003
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30			0003
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5907			0003
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ.FT	645			0003
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	79753			0003
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	58			0003
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	299			0003
70400100	TEMPORARY CONCRETE BARRIER	FOOT	275			0003
72000100	SIGN PANEL - TYPE 1	SQ.FT	348		X	0003
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	8		X	0003
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	5		X	0003
72900100	METAL POST - TYPE A	FOOT	406		X	0003
72900200	METAL POST - TYPE B	FOOT	149		X	0003
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ.FT	322		X	0003
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34685		X	0003
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2086		X	0003
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	191		X	0003
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	784		X	0003
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	208		X	0003
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	132	*	X	0003
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	44		X	0003
78300100	PAVEMENT MARKING REMOVAL	SQ.FT	13576		X	0003
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		X	0021
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1287		X	0021
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	51		X	0021
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	113		X	0021
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	578		X	0021
81400100	HANDHOLE	EACH	6		X	0021
81400200	HEAVY-DUTY HANDHOLE	EACH	4		X	0021
81400300	DOUBLE HANDHOLE	EACH	2		X	0021
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1029		X	0021
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	2		X	0021
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1		X	0021
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	899		X	0021

PI NO	DESCRIPTION	UNIT	QTY	SPECIAL PROVISION	SPECIALTY ITEM	CONSTRUCTION CODE
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	381		X	0021
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2665		X	0021
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1777		X	0021
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2333		X	0021
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	53		X	0021
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	853		X	0021
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		X	0021
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		X	0021
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1		X	0021
87704220	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT. (SPECIAL)	EACH	1	*	X	0021
87704230	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 62 FT. (SPECIAL)	EACH	1	*	X	0021
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20		X	0021
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		X	0021
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26	*	X	0021
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	42	*	X	0021
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		X	0021
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		X	0021
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4		X	0021
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12		X	0021
88500100	INDUCTIVE LOOP DETECTOR	EACH	8		X	0021
88600100	DETECTOR LOOP, TYPE I	FOOT	648		X	0021
88700200	LIGHT DETECTOR	EACH	2		X	0021
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		X	0021
A2004412	TREE, GINKGO BILOBA (GINKGO), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	44		X	0003
A2004814	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	42		X	0003
B2005714	TREE, PYRUS CALLERYANA CHANTICLEER CHANTICLEER CALLERY PEAR), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	40		X	0003
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	381	*	X	0021
X2080250	TRENCH BACKFILL, SPECIAL	CU YD	395	*		0003
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ.YD	1951	*		0003
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	9	*		0003
X6060340	GUTTER OUTLET (SPECIAL)	EACH	2	*		0003
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L.SUM	1	*		0003
X7010237	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL DA	1188	*		0003
X7040305	TEMPORARY CONCRETE BARRIER, TERMINAL SECTION (SPECIAL)	EACH	1	*		0003
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABLES SPECIAL	EACH	1	*	X	0021
XX005937	LED INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	4	*	X	0021
Z0001050	AGGREGATE SUBGRADE 12"	SQ.YD	52919	*		0003
Z0013798	CONSTRUCTION LAYOUT	L.SUM	1			0003
Z0019600	DUST CONTROL WATERING	UNIT	156	*		0003
Z0022800	FENCE REMOVAL	FOOT	4125	*		0003
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	7622	*		0003
Z0062456	TEMPORARY PAVEMENT	SQ.YD	10117	*		0003
Z0076600	TRAINEES	HOURL	1500	*		0042

FILE NAME = F:\070116\cad\phase 2\dwg\070116-sht-ach\duledgn
 USER NAME = #USER#
 PLOT SCALE = #SCALE#
 PLOT DATE = 1/6/2012

DESIGNED - CM
 DRAWN - JM
 CHECKED - CM
 DATE - FEBRUARY 2009
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION



SUMMARY OF QUANTITIES
 PLAINFIELD NAPERVILLE RD AT 119TH ST / RODEO DR

SCALE: 1" = 20' SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	04-00036-22-TL	WILL	152	3A
CONTRACT NO. 63671				
ILLINOIS FED. AID PROJECT				