



PAVEMENT MARKING LEGEND

- (A) 2-4" YELLOW @ 11" C-C (TYP.)
- (B) 4" WHITE SKIP-DASH (10' DASH, 30' SPACE)
- (C) 4" WHITE EDGE LINE
- (D) 12" YELLOW DIAGONAL @ 45°, 30' C/C (TYP.) 5 MIN.
- (E) 6" WHITE LANE LINE
- (F) 24" WHITE STOP BAR (TYP.)
- (G) 8" WHITE LETTERS & SYMBOLS (TYP.)
- (H) 4" YELLOW MEDIAN EDGE LINE
- (I) 6" WHITE SKIP-DASH (2' DASH, 6' SPACE)
- ▷ ONE-WAY CRYSTAL MARKER
- ▶ ONE-WAY AMBER MARKER
- ◆ TWO-WAY AMBER MARKER
- ✕ REMOVE SIGN PANEL ASSEMBLY
- [M] RELOCATE SIGN PANEL ASSEMBLY
- PROPOSED SIGN

NOTE:
ALL RAISED REFLECTIVE PAVEMENT MARKERS USED WITH SKIP DASHES SHALL BE CENTERED IN THE GAP BETWEEN SEGMENTS, AND OFFSET 4 INCHES FROM THE CENTERLINE OF THE DASH TO MATCH THE EXISTING MARKERS ON THE COUNTY HIGHWAY.

FILE NAME = P:\078116\oad\phase 2\dwg\078116-shr-pvm\m.k.dgn	USER NAME = #USER#	DESIGNED - CM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	HLR	PAVEMENT MARKING - PLAINFIELD NAPERVILLE ROAD PLAINFIELD NAPERVILLE RD AT 119TH ST / RODEO DR	F.A.I. RTE. 324	SECTION 04-00036-22-TL	COUNTY WILL	TOTAL SHEETS 152	SHEET NO. 55		
PLT SCALE = #SCALE#	PLT DATE = 1/5/2012	DRAWN - JM	REVISED -				SCALE: 1" = 40'	SHEET NO. 1 OF 1 SHEETS	STA. 204+50 TO STA. 245+00	CONTRACT NO. 63671		ILLINOIS FED. AID PROJECT	
		CHECKED - CM	REVISED -										
		DATE - FEBRUARY 2009	REVISED -										