

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL	80% FEDERAL	
					20% STATE	20% STATE	
					0001	0008	0008
					ROADWAY	US RTE 20 OVER PECATONICA RIVER S.N. 089-0082	US RTE 20 OVER JANE ADDAMS TRAIL SN. 089-0083
	542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	88	88		
	5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	449	449		
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
	54215547	METAL END SECTIONS 12"	EACH	12	12		
	54240205	INLET BOX, STANDARD 542546	EACH	2	2		
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	51	51		
	60100080	FRENCH DRAINS	CU YD	39	39		
	60100945	PIPE DRAINS 12"	FOOT	418	418		
	60107600	PIPE UNDERDRAINS 4"	FOOT	23,053	23,053		
	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	950	950		
	60240361	INLETS, TYPE B, WITH MEDIAN INLET (604101)	EACH	1	1		
	60600095	CLASS 51 CONCRETE (OUTLET)	CU YD	2	2		
	60900240	TYPE C INLET BOX, STANDARD 609006	EACH	3	3		
	60602500	CONCRETE GUTTER, TYPE A	FOOT	44.5	44.5		
	60900315	TYPE D INLET BOX, STANDARD 609006	EACH	9	9		
	60900515	CONCRETE THRUST BLOCKS	EACH	6	6		
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1037.5	1037.5		
*	63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	3,062.5	3,062.5		
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6		
*	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	6	6		
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
*	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4		
	63200310	GUARDRAIL REMOVAL	FOOT	1,027	1,027		
	63301210	REMOVE AND REERECT STEEL PLATE BEAM	FOOT	1306	1306		
	63500105	DELINEATORS GUARD RAIL, TYPE A	EACH	80	80		
	64200116	SHOULDER RUMBLE STRIPS, 16"	FOOT	65,098	65,098		
	64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
	66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	40	40		
	67100100	MOBILIZATION	L SUM	1	1		
	70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2	2		

△ NON-PARTICIPATING ITEM (100% STATE)
 • SPECIALITY ITEM

PARSONS BRINCKERHOFF
 380 West Monroe St. Suite 900
 Chicago, IL 60606, (312) 782-8150

USER NAME = MMS	DESIGNED - MMS	REVISED -
PLOT SCALE = 5/8" = 1' IN.	DRAWN - MMS	REVISED -
PLOT DATE = 9/28/11	CHECKED - RMH	REVISED -
	DATE - 12/02/2011	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A. RTE. 301	SECTION 177-2-1	COUNTY STEPHENSON	TOTAL SHEETS 211	SHEET NO. 7
FINAL SUBMITTAL			CONTRACT NO. 64860	
ILLINOIS FED. AID PROJECT P-92-014-03				

△ Rev. 2-22-12

T:\SERV\CH\1\PAV_Plan\28\PAVSOB08.dgn