

X4400110		TEMPORARY PAVEMENT REMOVAL				SQ YD	747
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY
	FT			FT			SQ YD
637+30.00	2.0		637+87.07	2.0	CT	CROSS OVER	13
637+87.07	2.0		639+62.85	16.0	CT	CROSS OVER	176
639+62.85	16.0		641+70.49	16.0	CT	CROSS OVER	369
641+70.49	16.0		643+48.31	2.0	CT	CROSS OVER	178
643+48.31	2.0		644+00.00	2.0	CT	CROSS OVER	11
TOTAL							747

X7240300		SIGN REMOVAL			EACH	1
STATION	OFFSET	LT/RT	TYPE	LOCATION	QUANTITY	
					EACH	
624+91.07	18.50	LT		WB INSIDE SHOULDER	1	
TOTAL						1

X7800605		URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS				SQ FT	84
STATION	OFFSET	TO	LT/RT	COLOR	DESCRIPTION	QUANTITY	
	FT					FOOT	
477+50.00	47		LT	WHITE	WB TRAVEL LANES	42	
482+50.00	49		LT	WHITE	WB TRAVEL LANES	42	
TOTAL							84

X7800610		URETHANE PAVEMENT MARKING - LINE 4"				FOOT	74,730	
STATION	OFFSET	TO	STATION	OFFSET	LT/RT	COLOR	DESCRIPTION	QUANTITY
	FT			FT				FOOT
463+36.08	27		466+11.08	27	RT	WHITE	WB TRAVEL LANES	275
485+00.00	51		666+41.00	51	LT	WHITE	WB TRAVEL LANES	18,141
463+36.08	51		640+25.00	51	RT	WHITE	EB TRAVEL LANES	17,689
463+36.08	39		468+25.32	39	RT	YELLOW	EB/WB TRAVEL LANES	489
463+36.08	40		468+25.32	40	RT	YELLOW	EB/WB TRAVEL LANES	489
68+20.71	18		70+34.00	16	LT	DOUBLE YELLOW	GORE	427
70+34.00	16		72+63.90	24	RT	YELLOW	WB TRAVEL LANES	230
72+63.90	24		77+00.00	24	RT	YELLOW	WB TRAVEL LANES	436
468+25.32	39		471+38.61	39	RT	DOUBLE YELLOW	GORE	627
471+38.61	39		472+38.61	27	RT	DOUBLE YELLOW	TAPER	200
477+00.00	27		666+41.00	27	LT	YELLOW	WB TRAVEL LANES	18,941
472+38.61	27		640+25.00	27	RT	YELLOW	EB TRAVEL LANES	16,786
TOTAL								74,730

X7800630		URETHANE PAVEMENT MARKING - LINE 6"				FOOT	8,832
STATION	TO	STATION	LT/RT	RATIO	DESCRIPTION	QUANTITY	
						FOOT	
471+38.61		536+91.95	RT	0.25	EB TRAVEL LANES	1,638	
536+91.95		545+08.85	RT	0.25	EB TRAVEL LANES	204	
545+08.85		568+97.70	RT	0.25	EB TRAVEL LANES	597	
568+97.70		571+03.01	RT	0.25	EB TRAVEL LANES	51	
571+03.01		640+25.00	RT	0.25	EB TRAVEL LANES	1,730	
482+00.00		536+51.33	LT	0.25	WB TRAVEL LANES	1,363	
536+51.33		544+68.24	LT	0.25	WB TRAVEL LANES	204	
544+68.24		568+84.90	LT	0.25	WB TRAVEL LANES	604	
568+84.90		570+90.20	LT	0.25	WB TRAVEL LANES	51	
570+90.20		666+41.00	LT	0.25	WB TRAVEL LANES	2,388	
TOTAL							8,832

X7800640		URETHANE PAVEMENT MARKING - LINE 8"			FOOT	1,889
STATION	TO	STATION	LT/RT	COLOR	DESCRIPTION	QUANTITY
						FOOT
466+11.08		485+00.00	LT	WHITE	WB TRAVEL LANES	1,889
TOTAL						1,889

X7800650		URETHANE PAVEMENT MARKING - LINE 12"			FOOT	93
STATION	TO	STATION	LT/RT	COLOR	DESCRIPTION	QUANTITY
						FOOT
469+10.49		469+18.54	RT	YELLOW	GORE STRIPES	11
469+37.88		469+48.47	RT	YELLOW	GORE STRIPES	15
469+65.26		469+78.40	RT	YELLOW	GORE STRIPES	19
469+92.64		470+08.33	RT	YELLOW	GORE STRIPES	22
470+20.02		470+38.26	RT	YELLOW	GORE STRIPES	26
TOTAL						93

X7830070		GROOVING FOR RECESSED PAVEMENT MARKING 5"				FOOT	70,641	
STATION	OFFSET	TO	STATION	OFFSET	LT/RT	COLOR	DESCRIPTION	QUANTITY
	FT			FT				FOOT
463+36.08	27		466+11.08	27	RT	WHITE	WB TRAVEL LANES	275
485+00.00	51		536+45.09	51	LT	WHITE	WB TRAVEL LANES	5,145
544+61.99	51		568+82.92	51	LT	WHITE	WB TRAVEL LANES	2,421
570+88.23	51		666+41.00	51	LT	WHITE	WB TRAVEL LANES	9,553
463+36.08	39		468+25.32	39	RT	YELLOW	EB/WB TRAVEL LANES	489
463+36.08	40		468+25.32	40	RT	YELLOW	EB/WB TRAVEL LANES	489
68+20.71	18		70+34.00	16	RT	YELLOW	GORE	427
70+34.00	16		72+63.90	24	RT	YELLOW	WB TRAVEL LANES	230
72+63.90	24		77+00.00	24	RT	YELLOW	WB TRAVEL LANES	436
468+25.32	39		471+38.61	39	RT	YELLOW	GORE	627
471+38.61	39		472+38.60	27	RT	YELLOW	GORE	200
477+00.00	27		536+57.58	27	LT	YELLOW	WB TRAVEL LANES	5,958
544+74.48	27		568+86.87	27	LT	YELLOW	WB TRAVEL LANES	2,412
570+92.17	27		666+41.00	27	LT	YELLOW	WB TRAVEL LANES	9,549
472+38.61	27		536+85.70	27	RT	YELLOW	EB TRAVEL LANES	6,447
545+02.60	27		568+95.73	27	RT	YELLOW	EB TRAVEL LANES	2,393
571+01.04	27		640+25.00	27	RT	YELLOW	EB TRAVEL LANES	6,924
463+36.08	51		536+98.19	51	RT	WHITE	EB TRAVEL LANES	7,362
545+15.09	51		568+99.68	51	RT	WHITE	EB TRAVEL LANES	2,385
571+04.98	51		640+25.00	51	RT	WHITE	EB TRAVEL LANES	6,920
TOTAL								70,641

X7830074		GROOVING FOR RECESSED PAVEMENT MARKING 7"			FOOT	7,660
STATION	TO	STATION	LT/RT	RATIO	DESCRIPTION	QUANTITY
471+38.61		536+91.95	RT	0.25	EB TRAVEL LANES	1,638
545+08.85		568+97.70	RT	0.25	EB TRAVEL LANES	597
571+03.01		640+25.00	RT	0.25	EB TRAVEL LANES	1,730
482+00.00		536+51.33	LT	0.25	WB TRAVEL LANES	1,363
544+68.24		568+84.90	LT	0.25	WB TRAVEL LANES	604
570+90.20		640+00.00	LT	0.25	WB TRAVEL LANES	1,727
TOTAL						7,660

T:\LIBRARY\Civil\PAV_P\Items\228\PAV\SCHED13.dgn



USER NAME = MMS	DESIGNED - MMS	REVISED -
PLOT SCALE = 50.0000 / 1 IN.	DRAWN - MMS	REVISED -
PLOT DATE = 9/28/11	CHECKED - RMH	REVISED -
	DATE - 12/02/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 13 OF 16 SHEETS STA. TO STA.

F.A. RTE. 301	SECTION 177-2-1	COUNTY STEPHENSON	TOTAL SHEETS 211	SHEET NO. 27
FINAL SUBMITTAL			CONTRACT NO. 64960	
[ILLINOIS] FED. AID PROJECT P-92-014-03				

Rev. 2-22-12