

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	
					0001	0008	0008
					ROADWAY	US RTE 20 OVER PECATONICA RIVER S.N. 089-0082	US RTE 20 OVER JANE ADDAMS TRAIL S.N. 089-0083
	20200100	EARTH EXCAVATION	CU YD	25,920	25,920		
*	20200200	ROCK EXCAVATION	CU YD	11,260	11,260		
	20800150	TRENCH BACKFILL	CU YD	39	39		
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	6,950	6,950		
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12,930	12,930		
	25000210	SEEDING, CLASS 2A	ACRE	11.0	11.0		
	25000310	SEEDING, CLASS 4	ACRE	1.00	1.00		
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,077	1,077		
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,077	1,077		
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,077	1,077		
△	25000750	MOWING	ACRE	12.0	12.0		
	25100115	MULCH, METHOD 2	ACRE	8.5	8.5		
	25100630	EROSION CONTROL BLANKET	SQ YD	40,802	40,802		
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	427	427		
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,565	2,565		
	28000400	PERIMETER EROSION BARRIER	FOOT	5,127	5,127		
	28000500	INLET AND PIPE PROTECTION	EACH	15	15		
	28001000	AGGREGATE (EROSION CONTROL)	TON	61	61		
	28100107	STONE RIPRAP, CLASS A4	SQ YD	71	71		
	28200200	FILTER FABRIC	SQ YD	71	71		
	31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	72,613	72,613		
	31100935	SUBBASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	3,500	3,500		
	31100965	SUBBASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	2,835	2,835		
	31100975	SUBBASE GRANULAR MATERIAL, TYPE A 30"	SQ YD	6,000	6,000		
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	69.7	69.7		

△ NON-PARTICIPATING ITEM (100% STATE)
 * SPECIALTY ITEM

T:\JES14A\Civil\PAV_Plane\Z08PAV5000.dgn

PARSONS BRINCKERHOFF
 280 West Monroe St. Suite 900
 Chicago, IL 60606, (312) 782-8180

USER NAME = MMS	DESIGNED - MMS	REVISED -
PLOT SCALE = 50.00' / IN.	DRAWN - MMS	REVISED -
PLOT DATE = 9/28/11	CHECKED - RMH	REVISED -
	DATE - 12/02/2011	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE	SHEET NO. 1 OF 5 SHEETS	STA. TO STA.	F.A. RTE. 301	SECTION 177-2-1	COUNTY STEPHENSON	TOTAL SHEETS 211	SHEET NO. 5
			FINAL SUBMITTAL		CONTRACT NO. 64860		
			ILLINOIS FED. AID PROJECT P-92-014-03				