

EARTHWORK SCHEDULE

LOCATION			MOT STAGES	EARTH EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 25%) (CU YD)	EMBANKMENT (CU YD)	ROCK EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION (CU YD)	TOPSOIL TO BE USED IN TOPSOIL PLACEMENT (ADJ. FOR SHRINKAGE 25%) (CU YD)	TOPSOIL PLACEMENT (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL FURNISH AND PLACE, 4" (SQ YD)
US 20 MAINLINE													
463+30.00	TO	471+00.00	STAGE IA	233	175	571	0	-396	213	160	213	-53	479
471+00.00	TO	473+25.00		58	45	84	0	-39	51	38	51	-13	115
637+30.00	TO	644+00.00		150	110	354	0	-244	123	92	123	-31	276
66+07.35	TO	71+00.00	STAGE I	1,324	993	1,874	0	-881	1,236	930	346	584	
71+00.00	TO	77+00.00		3,135	2,351	4,944	0	-2,593	4,665	3,500	504	2,996	
477+00.00	TO	486+00.00		1,519	1,139	170	0	970	0	0	266	-266	
486+00.00	TO	501+00.00		3,879	2,909	426	0	2,483	0	0	539	-539	
501+00.00	TO	516+00.00		2,785	2,089	560	0	1,529	0	0	603	-603	
516+00.00	TO	531+00.00		1,666	1,249	396	0	853	0	0	394	-394	
531+00.00	TO	546+00.00		664	498	202	0	296	0	0	192	-192	
546+00.00	TO	561+00.00		1,977	1,483	128	0	1,355	0	0	221	-221	
561+00.00	TO	576+00.00		759	569	280	0	289	0	0	300	-300	
576+00.00	TO	590+00.00		1,751	1,314	315	0	999	0	0	445	-445	
590+00.00	TO	604+00.00		1,152	864	533	0	331	0	0	505	-505	
604+00.00	TO	619+00.00		1,042	781	685	0	96	0	0	520	-520	3643
619+00.00	TO	634+00.00		3,149	2,362	1,712	2,036	2,685	536	400	770	-370	6518
634+00.00	TO	644+00.00		1	1	201	9,224	9,023	523	390	954	-564	1897
463+30.00	TO	471+00.00		STAGE II	396	0	0	0	396	0	0		
471+00.00	TO	473+25.00	39		0	0	0	39	0	0			
637+30.00	TO	644+00.00	244		0	0	0	244	0	0			
TOTAL:				25,920	18,935	13,435	11,260	17,435	7,350	5,515	6,950	-1,440	12,930

NOTE:
 1. CONTRACTOR MAY ROUGH GRADE AND UTILIZE GRADE FROM STA. 501+00 TO 516+00 AND FROM STA. 634+00 TO 644+00 AS BORROW LOCATIONS FOR STAGE IA.
 2. EXISTING TOP SOIL REMOVAL SHALL BE USED FOR 12" TOPSOIL PLACEMENT FOR ROCK CUT DITCHES AND BENCHES.

PARSONS
BRINCKERHOFF
 280 West Monroe St., Suite 900
 Chicago, IL 60606, (312) 782-8150

USER NAME = MMS	DESIGNED - MS	REVISED -
DRAWN - MS	CHECKED - RH	REVISED -
DATE - 12/02/2011		

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

EARTHWORK SCHEDULE	
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS
STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2-1	STEPHENSON	211	31
FINAL SUBMITTAL		CONTRACT NO. 64860		
ILLINOIS FED. AID PROJECT P-92-014-03				