

CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	ACNHF		ACDHF			
				80% FED / 20% STATE		80% FED / 20% STATE			
				ROADWAY 0004		BRIDGE 0014			
				SN 043-0002 SN 043-0003	SN 043-0004 SN 043-0005	SN 043-0006	SN 043-0007		
20100500	TREE REMOVAL, ACRES	ACRE	0.50	0.50					
20200100	EARTH EXCAVATION	CU YD	865	865					
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5,700	5,700					
* 21400100	GRADING AND SHAPING DITCHES	FOOT	300	300					
* 25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25					
Δ 25000750	MOWING	ACRE	1.25	1.25					
* 25100630	EROSION CONTROL BLANKET	SQ YD	5,505	5,505					
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	375	375					
* 28000305	TEMPORARY DITCH CHECKS	FOOT	8	8					
28000400	PERIMETER EROSION BARRIER	FOOT	8,447	8,447					
28000500	INLET AND PIPE PROTECTION	EACH	6	6					
28100107	STONE RIPRAP, CLASS A4	SQ YD	46	46					
28100109	STONE RIPRAP, CLASS A5	SQ YD	12,803		3,420	7,282		2,101	
28200200	FILTER FABRIC	SQ YD	12,849	46	3,420	7,282		2,101	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	7	7					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9					
40600300	AGGREGATE (PRIME COAT)	TON	46	46					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	148	148					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	481	481					
40600990	TEMPORARY RAMPS	SQ YD	853	853					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,608	1,608					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,273	1,273					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2	2					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	419	419					
44000100	PAVEMENT REMOVAL	SQ YD	271	271					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SQ YD	14,568	14,568					
44000300	CURB REMOVAL	FOOT	230	230					

* SPECIALTY ITEM
Δ 100% STATE

USER NAME = #OPERATOR#	DESIGNED -	REVISED -
FILE NAME = #FILES#	CHECKED -	REVISED -
PLOT DATE = Thu Dec 08 14:12:26	DRAWN -	REVISED -
PLOT TIME = #TIME#	CHECKED -	REVISED -

WHKS & CO.
ENGINEERING
1701 ROUTE 35 NORTH
EAST DUBUQUE, IL 61025
(815) 747-8833
DESIGN FIRM #184001036

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US 20
SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(43B,44B,44HB,45B)D	JO DAVIESS	309	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64C94	