LOCATION			TYPE	COLOR	70300100 SHORT TERM PAVEMENT MARKING	70300220 TEMPORARY PAVEMENT MARKING - LINE 4"	70301000 WORK ZONE PAVEMENT MARKING REMOVAL	78008210 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	78008230 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	78008240 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	78100100 RAISED REFLECTIVE PAVEMENT MARKERS	78300100 PAVEMENT MARKING REMOVAL	78300100 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STATION	STATION	OFFSET			(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(SQ FT)	(EACH)
SN 043-0005													
PRE-STAGE													
324+82	338+08	CL											17
STAGE 1													
325+95	327+25	LT	SOLID	WHITE		130	43					44	
327+25	331+05	LT	SOLID	WHITE		380	127					127	
331+05	332+95	LT	SOLID	WHITE		190	63					64	
325+95	327+25	LT	SOLID	YELLOW		130	43					44	
327+25	331+05	LT	SOLID	YELLOW		380	127					127	
331+05	332+95	LT	SOLID	YELLOW		190	63					64	
332+95	337+95	CL	SOLID	YELLOW		500	167					167	
STAGE 2													
325+30	332+95	RT	SOLID	WHITE		765	255						
325+30	332+95	RT	SOLID	YELLOW		765	255						
332+95	337+95	CL	SOLID	WHITE		500	167						
STAGE 3													
324+82	338+08	CL	SKIP DASH	WHITE	188		63						
STAGE 4													
324+82	338+08	LT	SOLID	WHITE				1,326					
324+82	338+08	CL	SKIP DASH	WHITE					340		17		
324+82	338+08	RT	SOLID	YELLOW				1,326					
SUBTOTAL					188	3,930	1,373	2,652	340	0	17	637	17