


LOCATION	20200100	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE(+) AND SHORTAGE (-)	21101615
	EARTH EXCAVATION				TOPSOIL FURNISH AND PLACE, 4"
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(SQ YD)
SN 043-0002					
STA. 221+04 TO STA. 225+26.82	124	93	138	-45	802
STA. 226+56.29 TO STA. 228+60	48	36	27	9	501
SN 043-0003					
STA. 222+40 TO STA. 224+66.86	31	23	12	11	97
STA. 225+95.78 TO STA. 229+69	75	56	27	29	374
SN 043-0004					
STA. 332+72 TO STA. 336+16.73	63	47	22	25	390
STA. 338+14.46 TO STA. 344+33	119	89	116	-27	629
SN 043-0005					
STA. 324+82 TO STA. 327+91.87	63	47	8	39	353
STA. 329+89.60 TO STA. 338+08	115	86	83	3	1,253
SN 043-0006					
STA. 412+90 TO STA. 413+78.31	18	14	9	5	126
STA. 415+06.31 TO STA. 419+11	71	53	21	32	498
SN 043-0007					
STA. 482+06.00 TO STA. 485+99.87	94	71	17	54	472
STA. 488+11.29 TO STA. 492+42.00	44	33	7	26	205
TOTAL	865	648	487	161	5,700

SHRINKAGE FACTOR FOR EARTH EXCAVATION = 25%

LOCATION	OFFSET	35101400	40800050	48101200	48102100
		AGGREGATE BASE COURSE, TYPE B	INDICENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SHOULDERS, TYPE B	AGGREGATE WEDGE SHOULDER, TYPE B
		(TON)	(TON)	(TON)	(TON)
SN 043-0002					
STA. 221+04 TO STA. 221+90	RT				2
STA. 226+90.43 TO STA. 228+60	LT			18	
STA. 227+04.01 TO STA. 228+60	RT			16	
SN 043-0003					
STA. 222+40 TO STA. 224+26.64	LT			21	
STA. 222+40 TO STA. 224+36.89	RT				7
STA. 226+43.48 TO STA. 226+85	RT			4	
STA. 226+85 TO STA. 229+69	RT				5
SN 043-0004					
STA. 337+98.50	LT	7	2		
STA. 338+54.71 TO STA. 338+65	LT			1	
STA. 338+65 TO STA. 344+33	LT				14
SN 043-0005					
STA. 334+18 TO STA. 338+08	RT				8
SN 043-0006					
STA. 418+61 TO STA. 419+11	LT				1
SN 043-0007					
STA. 482+06 TO STA. 482+26	RT				1
STA. 488+55.57 TO STA. 489+00	LT			4	
STA. 489+00 TO STA. 492+31	LT				7
TOTAL		7	2	64	45

USER NAME = #OPERATOR#	DESIGNED -	REVISED -		1701 ROUTE 35 NORTH EAST DUBUQUE, IL 61025 (815) 747-8833 DESIGN FIRM #184001038	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 20 SCHEDULE OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE NAME = #FILES#	CHECKED -	REVISED -						301	(43B,44B,44HB,45B/D)	JO DAVIESS	309	33
PLOT DATE = Thu Dec 08 10:27:00	DRAWN -	REVISED -						CONTRACT NO. 64C94				
PLOT TIME = #TIME#	CHECKED -	REVISED -						ILLINOIS FED. AID PROJECT				
					SCALE: NTS	SHEET NO. 12 OF 18 SHEETS	STA.	TO STA.				