

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	60% FED / 20% STATE
				CONSTR. CODE	
				0005	ROADWAY
20400800	FURNISHED EXCAVATION	CU YD	24		24
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4		4
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4		4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4		4
25200110	SODDING, SALT TOLERANT	SQ YD	266		266
25200200	SUPPLEMENTAL WATERING	UNIT	2		2
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24139		24139
40600300	AGGREGATE (PRIME COAT)	TON	282		282
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	48		48
40600725	POLYMERIZED LEVELING BINDER (HAND METHOD), N50	TON	67		67
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3111		3111
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600990	TEMPORARY RAMP	SQ YD	1261		1261
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	10653		10653
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1617		1617
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1054		1054
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	10149		10149
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	200		200
42400800	DETECTABLE WARNINGS	SQ FT	1733		1733
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	12232		12232
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	114198		114198
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	11534		11534
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1577		1577
44003100	MEDIAN REMOVAL	SQ FT	30		30
44000600	SIDEWALK REMOVAL	SQ FT	10344		10344
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SQ YD	272		272
44201381	CLASS C PATCHES, TYPE III, 12 INCH	SQ YD	32		32
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	162		162
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	20808		20808
48101200	AGGREGATE SHOULDERS, TYPE B	TON	300		300
56109210	WATER VALVES TO BE ADJUSTED	EACH	78		78