

SUMMARY OF QUANTITIES				80% FED. 20% STATE
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	0005	
			TOTAL QUANT	
20200100	EARTH EXCAVATION	CU YD	7.2	
20400800	FURNISHED EXCAVATION	CU YD	21	
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	
• 25100630	EROSION CONTROL BLANKET	SQ YD	252	
• 25200110	SODDING, SALT TOLERANT	SQ YD	48	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	16	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8,013	
40600300	AGGREGATE (PRIME COAT)	TON	125	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	18	
40600725	POLYMERIZED LEVELING BINDER (HAND METHOD), N50	TON	30	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	2,509	
40600895	CONSTRUCTING TEST STRIP	EACH	2	
40600990	TEMPORARY RAMP	SQ YD	422	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5,124	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	389	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,243	
42400800	DETECTABLE WARNINGS	SQ FT	112	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	62,825	

SUMMARY OF QUANTITIES				80% FED. 20% STATE
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	0005	
			TOTAL QUANT	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	120	
44000600	SIDEWALK REMOVAL	SQ FT	1,076	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,251	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	120	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	
67100100	MOBILIZATION	L SUM	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,639	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37,654	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,537	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	738	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	75,308	
• 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	9,414	
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,314	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	87	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	276	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	276	
Z0034105	MATERIAL TRANSFER DEVICE	TON	5,124	

• SPECIALTY ITEMS

FILE NAME =	USER NAME = carpenterd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci\pw\work\p\dot\carpenterd\10176480	366644-sht-cover.dgn	DRAWN -	REVISED -		317	37 RS-3	IROQUOIS	9	3			
	PLOT SCALE = 47.2222' / in.	CHECKED -	REVISED -						CONTRACT NO. 66644			
	PLOT DATE = 12/15/2011	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				