

MAINLINE SCHEDULE															
LOCATION	DESCRIPTION	LENGTH	AREA	HMA SURF REM 1 1/2"	HMA SURF REM 2 1/4"	HMA SURF CSE	LEVEL BINDER (MM)	BIT MATL (PR CT)	AGG (PR CT)	MIX FOR CRACKS, JTS & FLGWYS	LEVEL BINDER (HM)	TEMP RAMP	RUMBLE STRIP EACH	AGG SHLD TY B TON	
STA.		FOOT	SQ YD	SQ YD	SQ YD	TON	TON	GALLON	TON	TON	TON	SQ YD		TON	
KANKAKEE COUNTY															
352+33 TO 376+07.5		2374.5	6859.7		6859.7	576.2	288.1	891.8	13.7	2.1	3.4	21.7			
376+07.5 TO 377+97.5		190	665		665.0	55.9	27.9	86.5	1.3	0.2	0.3				
377+97.5 TO 379+23		125.5	571		571.0	48.0	24.0	74.2	1.1	0.2	0.3				
379+23 TO 381+59		236	1248.9		1248.9	104.9	52.5	162.4	2.5	0.4	0.6				
381+59 TO 382+91		132	560.3		560.3	47.1	23.5	72.8	1.1	0.2	0.3				
382+91 TO 384+41		150	516.7		516.7	43.4	21.7	67.2	1.0	0.2	0.3				
384+41 TO 393+25 BK		884	2553.8		2553.8	214.5	107.3	332.0	5.1	0.8	1.3				
387+42 AH TO 449+02		6160	17111.1		17111.1	1471.9	718.7	2224.4	34.2	5.1	8.6			350.8	
KANKAKEE COUNTY SUBTOTALS					17111.1	12975.4	2561.9	1263.7	3911.3	60.0	9.2	15.1	21.7	0	350.8
IROUOIS COUNTY															
449+02 TO 535+40		8638	23994.4		23994.4		2064.0	1007.8	3119.3	48.0	7.2	12.0		491.9	
535+40 TO 540+38		498	1826		1826.0		156.2	76.7	237.4	3.7	0.5	0.9			
540+38 TO 540+68	BUTT JOINT	30	110		110.0		9.4	4.6	14.3	0.2	0.0	14.4			
540+68 TO 542+58	S.N. 038-0206 OMISSION	190													
542+58 TO 542+88	BUTT JOINT	30	110		110.0		9.4	4.6	14.3	0.2	0.0	14.4			
542+88 TO 546+88		400	1466.7		1466.7		125.4	61.6	190.7	2.9	0.4	0.7			
546+88 TO 754+39		20751	57641.7		57641.7		4958.2	2421.0	7493.4	115.3	17.3	28.8		1181.7	
754+39 TO 756+24		185	678.3		678.3		58.0	28.5	88.2	1.4	0.2	0.3			
756+24 TO 756+54	BUTT JOINT	30	110		110.0		9.4	4.6	14.3	0.2	0.0	14.4			
756+54 TO 758+20	S.N. 038-0019 OMISSION	166													
758+20 TO 758+50	BUTT JOINT	30	110		110.0		9.4	4.6	14.3	0.2	0.0	14.4			
758+50 TO 760+63		213	781		781.0		66.8	32.8	101.5	1.6	0.2	0.4			
760+63 TO 827+26		6663	18508.3		18508.3		1592.1	777.3	2406.1	37.0	5.6	9.3		379.4	
827+26 TO 834+77	S.N. 038-2500	751	2523.1		2523.1		216.2	106.0	328.0	5.0	0.8	1.3		42.8	
834+77 TO 865+22		3045	8569.4		8569.4		736.9	359.9	1114.0	17.1	2.6	4.3	1		
865+22 TO 866+04	S.N. 038-0020	82	255.1		255.1		21.9	10.7	33.2	0.5	0.1	0.1			
866+04 TO 867+84		180	611.1		611.1		52.3	25.7	79.4	1.2	0.2	0.3		10.3	
867+84 TO 868+14	BUTT JOINT	30	96.7		96.7		8.3	4.1	12.6	0.2	0.0	16.1		1.7	
IROUOIS COUNTY SUBTOTALS					117391.8	0.0	10093.9	4930.5	15261.0	234.7	35.1	58.8	73.7	1	2107.8
TOTALS					134502.9	12975.4	12655.8	6194.2	19172.3	294.7	44.3	73.9	95.4	1	2458.6

EXPANSION JOINTS	
LOCATION	EXPANSION JOINT REHAB
STRUCTURE	FOOT
IROUOIS COUNTY	
SN 038-0017	50
SN 038-0206	50
SN 038-0019	51
SN 038-2500	25
SN 038-0020	54
TOTAL	230

MANHOLE SCHEDULE		
LOCATION	OFFSET	MANHOLE TO BE ADJUSTED
STA	LT/RT	EACH
KANKAKEE COUNTY		
STATION STREET	LT	1
CHAPEL STREET	LT	1
377+97	RT	1
379+25	RT	1
380+15	LT	1
SCHOOL RD	LT	3
TOTAL		8

FILE NAME =	USER NAME = corcoranlm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\corcoranlm\d0135018\066921-sht-schedule.dgn	DRAWN -	REVISED -	332					(4,5,H,K,C)-IRS-4		20	8	
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.			* KANKAKEE & IROUOIS CONTRACT NO. 66921						
PLOT DATE = 12/13/2011	DATE -	REVISED -				ILLINOIS FED. AID PROJECT						