

PAVEMENT MARKING														
LOCATION	DESCRIPTION	LENGTH	PAINT PAVEMENT MARKING LINE			PREFORMED PLASTIC PVMT MARK, TY B	THERMOPLASTIC PAVEMENT MARKING LINE							
			4 INCH		6 INCH	24 INCH	4 INCH	6 INCH		8 INCH	12 INCH		LETTERS & SYMBOLS	
			YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	& SYMBOLS	
STA		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	
KANKAKEE COUNTY														
352+33 TO 376+00	MAINLINE	2367						592						
376+00 TO 384+71	TURN LANE/MEDIAN	871				89	2454	172		524	32.2	147.7	156	
384+71 TO 393+25 BK	MAINLINE/NPZ EB	854					480			214				
387+42 AH TO 449+02	MAINLINE	6160		24640	3080									
KANKAKEE COUNTY SUBTOTALS			0	24640	3080	89	2934	172		806	524	32.2	147.7	156
IROQUOIS COUNTY														
449+02 TO 860+84	MAINLINE	41182		164728	20591									
860+84 TO 868+14	NO PASS ZONE SB	730	1460	2920	365									
STOP BARS AT US 52						160								
IROQUOIS COUNTY SUBTOTALS			1460	167648	20956	160	0	0	0	0	0	0	0	
TOTALS			1460	167648	20956	160	0	0	0	0	0	0	0	
TOTALS			193748	24036	249	2934	978	524	179.9	156				

NOTE: ADDITIONAL QUANTITY HAS BEEN INCLUDED TO ALLOW FOR TWO SEPARATE APPLICATIONS OF PAINT PAVEMENT MARKING LINE

TEMPORARY PAVEMENT MARKING													
LOCATION	DESCRIPTION	LENGTH	SHORT TERM PAVEMENT MARKING	WORK ZONE PVMT MARK REMOVAL	TEMPORARY PAVEMENT MARKING LINE								
					4 INCH		6 INCH		8 INCH	12 INCH		24 INCH	LETTERS & SYMBOLS
					YELLOW	WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE	SO FT
STA		FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT
KANKAKEE COUNTY													
352+33 TO 376+00	MAINLINE	2367	711	79			592						
376+00 TO 384+71	TURN LANE/MEDIAN	871	3285	365	2454			172	524	32.2	147.7	89	156
384+71 TO 393+25 BK	MAINLINE	854	255	28	480				214				
387+42 AH TO 449+02	MAINLINE	6160	1848	205		12320			1540				
KANKAKEE COUNTY SUBTOTALS			6099	677	2934	12320	2346	172	524	32.2	147.7	89	156
IROQUOIS COUNTY													
449+02 TO 860+84	MAINLINE	41182	12354	1373		82364	10296						
860+84 TO 868+14	NO PASS ZONE SB	730	219	24	730	1460	183						
STOP BARS AT US 52												160	
IROQUOIS COUNTY SUBTOTALS			12573	1397	730	83824	10479	0	0	0	0	160	0
TOTALS			18672	2074	99808	12997	524	179.9	249	156			

RAISED REFLECTIVE PAVEMENT MARKER				
LOCATION	RAISED REFLECTIVE PAVEMENT MARKER		RAISED REFL PVMT MARKER REMOVAL	PRISMATIC CURB REFLECTORS
	TWO-WAY AMBER	ONE-WAY CRYSTAL		
STA	EACH	EACH	EACH	EACH
KANKAKEE COUNTY				
352+33 TO 376+00	30		30	
376+00 TO 384+71	46	8	54	
380+40				15
384+71 TO 393+25 BK	11		11	
387+42 AH TO 449+02	77		62	
KANKAKEE COUNTY SUBTOTALS			172	157
IROQUOIS COUNTY				
449+02 TO 868+14	522		393	
IROQUOIS COUNTY SUBTOTALS			522	393
TOTALS			694	550