

ADJUSTMENTS		
LOCATION STATION	WATER VALVES TO BE ADJUSTED (EACH)	MANHOLES TO BE ADJUSTED (EACH)
BETWEEN IL 47 AND LIBERTY		2.0
BETWEEN LIBERTY AND BLACK		1.0
BETWEEN BLACK AND LISBON S		1.0
BETWEEN LISBON S AND LISBON N		0.0
BETWEEN LISBON N AND MICHAEL/UNION	1	1.0
SIDEROADS:		
BLACK N		1.0
LISBON N		3.0
MICHAEL		4.0
UNION	3	4.0
TOTALS	4	17

SIDEWALK SCHEDULE FOR NEW RAMP INSTALLATION									
LOCATION SIDE STREET QUAD	STANDARD NUMBER	PCC SIDEWALK 4"	DETECTABLE WARNINGS		CC&G (SPEC) FOOT	SIDEWALK REMOVAL SQ FT	CC&G REMOV (SPEC) FOOT	SOD, SALT TOLERANT SQ YD	SUPPLEMENTAL WATERING UNIT
			US6 ACCESS SQ FT	SIDE ROAD ACCESS SQ FT					
BLACK ST									
NW	424001 >5'	27.0		10.0	12.0	27.0	14.0	8.0	0.22
NE	424001 >5'	30.0		12.0	14.0	30.0	16.0	8.0	0.22
LISBON ST									
SW	424006	35.0		8.0	12.0	35.0	12.0	6.0	0.16
SE*	424006	70.0	10.0	11.0	18.0	70.0	18.0	10.0	0.27
NF	424006	74.0	11.0		9.0	74.0	9.0	4.0	0.11
CR RD27									
NW	424006	60.0		13.0	10.0	60.0	10.0	0.0	0.00
NF	424006	45.0		13.0	10.0	45.0	10.0	6.0	0.16
SW	424016	22.0		10.0	10.0	22.0	10.0		
UNION ST									
SW	424006	50.0		13.0	10.0	50.0	10.0	0.0	0.00
SF	424006	48.0		10.0	9.0	48.0	9.0	6.0	0.16
CRFEK DR									
NW	424016	25.0		10.0	9.0	25.0	9.0	6.0	0.16
NF	424016	25.0		10.0	9.0	25.0	9.0	6.0	0.16
DEFRPATH DR									
SE	424001 >5'	23.0		9.0	9.0	23.0	9.0	6.0	0.16
SW	424001 >5'	40.0		11.0	9.0	40.0	9.0	6.0	0.16
TOTAL(ALL URBAN)		574.0	21.0	140.0	150.0	574.0	154.0	72.0	1.9

* SE QUADRANT OF LISBON ST. HAS 2 SEPARATE H/C RAMPS

FILE NAME =	USER NAME = braboypc	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr\pw\work\p\dot\braboypc\0244830\036275-shr-cover.dgn	PLOT SCALE = 55.0605' / in.	DRAWN -	REVISED -			296	IO,P,O,GRS-3	GRUNDY	19	11	
PLOT DATE = 1/6/2012	DATE -	CHECKED -	REVISED -			CONTRACT NO. 66A75					
						ILLINOIS FED. AID PROJECT					