

ADJUSTMENT SCHEDULE						
LOCATION	MANHOLES TO BE ADJ	MANHOLES TO BE ADJ W/ NEW TY1 FRAME & LID	HANDHOLE TO BE ADJ	WATER VALVES TO BE ADJ	VALVE BOXES TO BE ADJ	INLET TO BE ADJ
	60255500	60255800	81400115	56109210	60266600	60260100
	EACH	EACH	EACH	EACH	EACH	EACH
BEGIN - IOWA AVE.	1				1	2
IOWA AVE - 12th AVE	2					
12th AVE. - WISCONSIN AVE.	1					3
WISCONSIN AVE. - 11th AVE.						
11th AVE. - MICHIGAN AVE.		1			1	3
MICHIGAN AVE. - 10th AVE.	1	1*				
10th AVE. - PENNSYLVANIA AVE.	4					2
PENNSYLVANIA AVE. - INDIANA AVE.	6	3*, 2			1	
INDIANA AVE. - 8th AVE.	2	1*			2	2
8th AVE. - ILLINOIS AVE.						2
ILLINOIS AVE. - MAIN ST.	3				2	6
WASHINGTON AVE. - 6th ST.			1		1	1
MAIN ST. - 7th AVE.	3	1*	1			
7th AVE. - 6th AVE.	7	3				4
6th ST - 7th ST	1	1			1	
7th ST - 8th ST	1					
8th ST - 9th ST		1				
9th ST - 10th ST		1				
10th ST - 5th AVE.						
5th AVE. - 11th ST	1					
11th ST - 12th ST	1					
12th ST - 1st AVE.	3			1		
TOTALS	37	15	2	1	9	25

*REPLACE NEW LIDS WITH MATCHING LETTERING "SANITARY"

PAVEMENT MARKING															
STATION	SHORT TERM PAVT MARK 4 IN	TEMP PAVT MARK L&S	TEMP PAVT MARK 4 IN	TEMP PAVT MARK 6 IN	TEMP PAVT MARK 8 IN	TEMP PAVT MARK 12 IN	TEMP PAVT MARK 24 IN	THERMO PLASTIC L&S	THERMO PLASTIC 4 IN	THERMO PLASTIC 6 IN	THERMO PLASTIC 8 IN	THERMO PLASTIC 12 IN	PREFORM PLASTIC PAVT TY B INLAID 24 IN	RAISED REFLECT MARK	RAISED REFLECT MARK REM
	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
1+00 - 5+79	678	15.6	1584	192	194	120	28	15.6	1584	192	194	120	28	20	
5+79 - 20+00	426	117.4	0	1166	0	432	99	117.4	0	1166	0	432	99	16	
20+01 - 22+92.5	372	15.6	440	426	80	426	23	15.6	440	426	80	426	23		
22+92.5 - 31+70	756	62.4	376	112	138	112	0	62.4	376	112	138	112	0		
31+70 - 34+55	348	61.2	316	358	67	358	115	61.2	316	358	67	358	115		
34+55 - 40+00	165	61.2	966	432	0	326	182	61.2	966	432	0	326	182		
40+00 - 82+11	1827	112.8	5607.0	1389.0	0.0	162.0	165.0	112.8	5607	1389	0	162	165	74	
TEMP PAINT PVT MARK QUANTITIES FOR 1 APPLICATION (LEVEL BINDER, AND AN ABBREVIATED APPLICATION FOR MILLING)															
SHORT TERM PAVT MARK QUANTITIES FOR 3 APPLICATION (MILLING, LEVEL BINDER, AND SURFACE)															
TOTALS	4572	446	9289	4075	479	1936	612	446	9289	4075	479	1936	612	110	118

TIE POINTS					
US RTE. 34	FROM ILL 251 TO FIRST AVE IN MENDOTA			LASALLE COUNTY	
STATION	DESCRIPTION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY
	W QTR COR SEC 33-36-1E	BRASS PLUG	TYPE 1	YES	2
14+39.20	NW COR SEC 34-36-1E	BRASS PLUG	TYPE 1	NO	2

NOTE: FOR ALL MONUMENT LOCATIONS SEE TIE SKETCHES

RESPONSIBILITY:
 1) RESIDENT TO RE-ESTABLISH MONUMENT
 2) RESIDENT TO RE-ESTABLISH MONUMENT AND FURNISH TIE SKETCHES TO D-3 PLATS AND PLANS (PAY ITEM REQUIRED, PERMANENT SURVEY MARKER, TYPE 1)