

LOCATION NO. 1					
COUNTY	LIVINGSTON	ROUTE	FAP 68	STATION	SN: 053-2012
DESCRIPTION OF WORK				UNIT	QUANTITY
STRUCTURE EXCAVATION				CU. YD.	18
EARTH EXCAVATION				CU. YD.	30
FURNISHED EXCAVATION				CU. YD.	48
HEAVY DUTY EROSION CONTROL BLANKET				SO. YD.	25
CONCRETE REMOVAL				CU. YD.	2.8
CONCRETE BOX CULVERTS				CU. YD.	2.8
REINFORCEMENT BARS (EPOXY COATED)				POUND	351
SHEET WATERPROOFING MEMBRANE SYSTEM				SO. YD.	6
TRAFFIC CONTROL AND PROTECTION STANDARD 701201				LUMP SUM	1
TEMPORARY CONCRETE BARRIER				FOOT	100
IMP ATTN TEMP SUN TL 3				EACH	2

LOCATION NO. 4					
COUNTY	LASALLE	ROUTE	FAP 46	STATION	SN: 050-2523
DESCRIPTION OF WORK				UNIT	QUANTITY
STRUCTURE EXCAVATION				CU. YD.	26
FURNISHED EXCAVATION				CU. YD.	26
HEAVY DUTY EROSION CONTROL BLANKET				SO. YD.	50
CONCRETE REMOVAL				CU. YD.	4
CONCRETE BOX CULVERTS				CU. YD.	4
REINFORCEMENT BARS (EPOXY COATED)				POUND	440
SHEET WATERPROOFING MEMBRANE SYSTEM				SO. YD.	6
TRAFFIC CONTROL AND PROTECTION STANDARD 701201				LUMP SUM	1

LOCATION NO. 2					
COUNTY	LIVINGSTON	ROUTE	FAP 68	STATION	SN: 053-2013
DESCRIPTION OF WORK				UNIT	QUANTITY
STRUCTURE EXCAVATION				CU. YD.	18
EARTH EXCAVATION				CU. YD.	30
FURNISHED EXCAVATION				CU. YD.	48
HEAVY DUTY EROSION CONTROL BLANKET				SO. YD.	25
CONCRETE REMOVAL				CU. YD.	2.1
CONCRETE BOX CULVERTS				CU. YD.	2.1
REINFORCEMENT BARS (EPOXY COATED)				POUND	274
SHEET WATERPROOFING MEMBRANE SYSTEM				SO. YD.	5
TRAFFIC CONTROL AND PROTECTION STANDARD 701201				LUMP SUM	1
RELOCATE TEMPORARY CONCRETE BARRIER				FOOT	100
RELOCATE IMP ATTN TEMP SUN TL 3				EACH	2

LOCATION NO. 5					
COUNTY	LASALLE	ROUTE	FAP 623	STATION	050-2589
DESCRIPTION OF WORK				UNIT	QUANTITY
STRUCTURE EXCAVATION				CU. YD.	9
FURNISHED EXCAVATION				CU. YD.	9
HEAVY DUTY EROSION CONTROL BLANKET				SO. YD.	25
CONCRETE REMOVAL				CU. YD.	1
CONCRETE BOX CULVERTS				CU. YD.	1
REINFORCEMENT BARS (EPOXY COATED)				POUND	103
SHEET WATERPROOFING MEMBRANE SYSTEM				SO. YD.	4
TRAFFIC CONTROL AND PROTECTION STANDARD 701201				LUMP SUM	1

LOCATION NO. 3					
COUNTY	LIVINGSTON	ROUTE	FAP 68	STATION	SN: 053-2014
DESCRIPTION OF WORK				UNIT	QUANTITY
STRUCTURE EXCAVATION				CU. YD.	9
EARTH EXCAVATION				CU. YD.	15
FURNISHED EXCAVATION				CU. YD.	24
HEAVY DUTY EROSION CONTROL BLANKET				SO. YD.	25
AGGREGATE SHOULDERS, TYPE B				CU. YD.	3
CONCRETE REMOVAL				CU. YD.	2
CONCRETE BOX CULVERTS				CU. YD.	2
STR REP CON DP = < 5				SO. FT.	18
REINFORCEMENT BARS (EPOXY COATED)				POUND	237
TEMPORARY SOIL RETENTION SYSTEM				SO. FT.	576
REM & REERECT SPBGR, TYPE A				FOOT	37.5
SHEET WATERPROOFING MEMBRANE SYSTEM				SO. YD.	6
TEMPORARY BRIDGE TRAFFIC SIGNALS				EACH	1
TRAFFIC CONTROL AND PROTECTION STANDARD 701321				LUMP SUM	1

LOCATION NO. 6					
COUNTY	GRUNDY	ROUTE	FAI 55	STATION	032-2519
DESCRIPTION OF WORK				UNIT	QUANTITY
STRUCTURE EXCAVATION				CU. YD.	26
FURNISHED EXCAVATION				CU. YD.	26
HEAVY DUTY EROSION CONTROL BLANKET				SO. YD.	25
CONCRETE REMOVAL				CU. YD.	1.6
CONCRETE BOX CULVERTS				CU. YD.	1.6
REINFORCEMENT BARS (EPOXY COATED)				POUND	155
SHEET WATERPROOFING MEMBRANE SYSTEM				SO. YD.	5
TRAFFIC CONTROL AND PROTECTION STANDARD 701406				LUMP SUM	1

FILE NAME =	USER NAME = peteljj	DESIGNED - YOGESH PATEL	REVISED -
c:\pwork\p\dot\peteljj\d0266509\0366	42-sheets.dgn	DRAWN - YOGESH PATEL	REVISED -
	PLOT SCALE = 100.0000 / 1 in.	CHECKED - RON WOODSHANK	REVISED -
	PLOT DATE = 1/31/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	VARIOUS	VARIOUS	40	6
			CONTRACT NO. 66B42	
ILLINOIS FED. AID PROJECT				