

SUMMARY OF QUANTITIES			
CONSTRUCTION CODE		100% STATE 0005	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	339.4
40600300	AGGREGATE (PRIME COAT)	TON	5.2
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.8
40600990	TEMPORARY RAMP	SQ YD	52
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	219.2
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0 N90	TON	328.9
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	2610.5
67100100	MOBILIZATION	LSUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2256
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3221
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	692
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	391
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	106
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	15
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	15

• SPECIALITY ITEMS

MAINLINE SCHEDULE										
LOCATION	DESCRIPTION	LENGTH	AREA	HMA SURF REM 3 3/4"	TEMP RAMP	BIT MATL (PR CT)	AGG (PR CT)	MIXTURES FOR CRACKS JOINTS AND FLANGEWAYS	POLY. LEVEL BINDER 2 1/4" (MM) N90	POLY. HMA SURF 1 1/2" CSE N90
STA.		FOOT	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON
BUREAU COUNTY- URBAN IL 89										
STA. 223+50 - STA. 230+87	LT START PROJECT	737	1187.4	1187.4	8.3	154.4	2.4	0.4	149.6	99.7
STA. 230+87 - STA. 232+85	LT	198	312	312.0	14.4	40.6	0.6	0.1	39.3	26.2
BUREAU COUNTY - URBAN US 6										
STA. 1806+35 - STA. 1807+63.8	LT END PROJECT	125	1111.1	1111.1	28.9	144.4	2.2	0.3	140.0	93.3
STA. 1807+63.8 - STA. 1810+21		261								
BUREAU COUNTY SUBTOTALS				2610.5	52.0	339.4	5.2	0.8	328.9	219.2
TOTALS				2610.5	52.0	339.4	5.2	0.8	328.9	219.2

PAVEMENT MARKING SCHEDULE										
LOCATION	SHORT-TERM PAVEMENT MARKING	THERMOPLASTIC PAVEMENT MARKING LETTERS & SYMBOLS	THERMOPLASTIC PAVEMENT MARKING LINE 4"	THERMOPLASTIC PAVEMENT MARKING LINE 8"	THERMOPLASTIC PAVEMENT MARKING LINE 12"	THERMOPLASTIC PAVEMENT MARKING LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		
STA. TO STA.	FOOT WHITE	SQ FT WHITE	FOOT YELLOW	FOOT WHITE	FOOT WHITE	FOOT WHITE	EACH CRYSTAL	EACH		
BUREAU COUNTY- IL 89										
STA. 223+50 TO STA. 230+87	1383	78	1267	650.98	396.3		11	11		
STA. 230+87 TO STA. 232+85	698.7	46.8	351	392.4	295.3		4	4		
BUREAU COUNTY- US 6										
STA. 1806+35 TO STA. 1807+63.8	174.33	15.6	203.7	355.6	391	56.1				
STA. 1807+63.8 TO STA. 1810+21	83.85		318	369.6	195	52.7				
TOTAL	2256	140	1822	1399	692	106	15	15		

FILE NAME =	USER NAME = Ferguson	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pwork\pwork\ferguson\02276878\066668-sht-cover.dgn		DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	BUREAU	6	3
PLOT SCALE = 50.0000' / in.		CHECKED -	REVISED -		CONTRACT NO. 66B68								
PLOT DATE = 12/15/2011		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								