

MOBILIZATION	
LOCATION	L SUM
ENTIRE PROJECT	1
TOTAL =	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	
LOCATION	EACH
ENTIRE PROJECT	1
TOTAL =	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	
LOCATION	EACH
ENTIRE PROJECT	1
TOTAL =	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	
LOCATION	L SUM
ENTIRE PROJECT	1
TOTAL =	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	
LOCATION	L SUM
ENTIRE PROJECT	1
TOTAL =	1

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DA
ENTIRE PROJECT	5
TOTAL =	5

TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	
LOCATION	EACH
ENTIRE PROJECT	1
TOTAL =	1

TEMPORARY RUMBLE STRIPS	
LOCATION	EACH
RT. STA. 174+57	1
RT. STA. 179+57	1
RT. STA. 184+57	1
LT. STA. 214+72	1
LT. STA. 219+72	1
LT. STA. 224+72	1
TOTAL =	6

PAVEMENT MARKING TAPE, TYPE III 4"			
LOCATION			FOOT
PRE-STAGE CONST.			
LT. STA. 192+17 TO LT. STA. 194+70	WHITE		253
LT. STA. 204+65 TO LT. STA. 207+62	WHITE		297
STAGE I			
RT. STA. 191+67 TO LT. STA. 194+70	WHITE		303
LT. STA. 193+47 TO LT. STA. 194+70	WHITE		123
LT. STA. 204+65 TO RT. STA. 207+12	WHITE		247
LT. STA. 204+65 TO LT. STA. 205+80	WHITE		115
STAGE II			
LT. STA. 192+47 TO RT. STA. 194+70	WHITE		223
RT. STA. 193+56 TO RT. STA. 194+70	WHITE		114
RT. STA. 204+65 TO LT. STA. 207+44	WHITE		279
RT. STA. 204+65 TO RT. STA. 205+86	WHITE		121
TOTAL =			2075

TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STAGE I	
STA. 193+15 TO STA. 200+15	700
STA. 201+40 TO STA. 206+15	475
LT. STA. 195+40 TO LT. STA. 197+15	175
LT. STA. 202+15 TO LT. STA. 203+90	175
TOTAL =	1525

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STAGE II	
STA. 193+53 TO STA. 200+15	662.5
STA. 201+40 TO STA. 205+77	437.5
TOTAL =	1100

SHORT TERM PAVEMENT MARKING		
LOCATION	NO. OF COURSES	FOOT
STA. 191+57 TO STA. 207+72	3	484.5
TOTAL =		484.5

TEMPORARY PAVEMENT MARKING - LINE 4"			
LOCATION	TYPE/COLOR		FOOT
LT. STA. 191+57 TO LT. STA. 207+72	EDGE LINE/WHITE		1615
CL STA. 191+57 TO STA. 207+72	SKIP DASH/YELLOW		410
RT. STA. 191+57 TO RT. STA. 207+72	EDGE LINE/WHITE		1615
TOTAL =			3640

CHANEABLE MESSAGE SIGN	
LOCATION	CAL MO
ENTIRE PROJECT (SEE SP)	0.5
TOTAL =	0.5

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
SHORT TERM PAVEMENT MARKING	54
TEMPORARY PAVEMENT MARKING - LINE 4"	1215
TOTAL =	1269

EPOXY PAVEMENT MARKING - LINE 4"		
LOCATION	TYPE/COLOR	FOOT
LT. STA. 191+57 TO LT. STA. 207+72	EDGE LINE/WHITE	1615
STA. 191+57 TO STA. 207+72	SKIP DASH/YELLOW	410
RT. STA. 191+57 TO RT. STA. 207+72	EDGE LINE/WHITE	1615
TOTAL =		3640

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA. 191+57 TO STA. 207+72	21
TOTAL =	21

PAVEMENT MARKING REMOVAL		
LOCATION	TYPE	SQ FT
PRE-STAGE		
STA. 191+57 TO STA. 207+72	CL SKIP - DASH	136.7
STAGE I		
LT. STA. 193+47 TO STA. 205+80	EDGE LINE	411.0
TOTAL =		547.7

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
STA. 191+57 TO STA. 207+72	21
TOTAL =	21

MOWING	
LOCATION	ACRE
STA. 193+11 TO STA. 206+24	1
TOTAL =	1

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	
LOCATION	SQ YD
STA. 195+00 TO STA. 204+35	3948
TOTAL =	3948

CONSTRUCTION LAYOUT	
LOCATION	L SUM
ENTIRE PROJECT	1
TOTAL =	1

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE I	
RT., STA. 193+15	1
RT., STA. 206+15	1
TOTAL =	2

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	
LOCATION	EACH
STAGE I	
LT. STA. 195+40	1
LT. STA. 197+15	1
STA. 200+15	1
STA. 201+40	1
LT. STA. 202+15	1
LT. STA. 203+90	1
TOTAL =	6

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE II	
STA. 200+15	1
STA. 201+40	1
TOTAL =	2

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STAGE II	
LT., STA. 193+53	1
LT., STA. 205+77	1
TOTAL =	2

MATERIAL TRANSFER DEVICE		
LOCATION	MATERIAL	TON
STA. 194+70 TO STA. 204+65	SURFACE (1 1/2")	242.2
TOTAL =		242.2