

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE			
				0004 ROADWAY	0011 STRUCTURE SN 055-0080	0011 STRUCTURE SN 055-0081	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	25	25			
20100500	TREE REMOVAL, ACRES	ACRE	0.1	0.1			
20200100	EARTH EXCAVATION	CU YD	3075	3075			
20300100	CHANNEL EXCAVATION	CU YD	2036	2036			
20400800	FURNISHED EXCAVATION	CU YD	4165	4165			
20800150	TRENCH BACKFILL	CU YD	76	76			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10656	10656			
X 25000210	SEEDING, CLASS 2A	ACRE	3.25	3.25			
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	290.0	290.0			
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	290.0	290.0			
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	290.0	290.0			
X 25000700	AGRICULTURAL GROUND LIMESTONE	TON	7	7			
X 25100115	MULCH, METHOD 2	ACRE	3.25	3.25			
X 25100630	EROSION CONTROL BLANKET	SQ YD	406	406			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	650	650			
28000315	AGGREGATE DITCH CHECKS	TON	80	80			
28000400	PERIMETER EROSION BARRIER	FOOT	1060	1060			
28000500	INLET AND PIPE PROTECTION	EACH	5	5			
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	160	160			
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	2311	698	854	759	
28200200	FILTER FABRIC	SQ YD	2858	1047	995	816	
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	4316	4316			
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	59	59			
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	1976	1976			
35100100	AGGREGATE BASE COURSE, TYPE A	TON	133	133			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	40	40			
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	24.1	24.1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2228	2228			
40600990	TEMPORARY RAMP	SQ YD	400	400			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	6720	6720			

X SPECIALTY ITEM

FILE NAME = P:\07files\078286\Phase2\CADD Sheets\06891-sht-summary.dgn	USER NAME = #USER#	DESIGNED -	REVISED - 12/12/11 (SRUCT #)
PLOT SCALE = 1/8" = 1'-0" IN.		DRAWN -	REVISED -
PLOT DATE = 12/13/2011		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: none SHEET NO. 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(38B-2)BR	MCDONOUGH	130	3
CONTRACT NO. 68691				
ILLINOIS FED. AID PROJECT				