

TABULATION OF SHOULDER QUANTITIES

LOCATION	WIDTH		HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 2"	HMA SURFACE REMOVAL, 3 3/4"	PAVED SHOULDER REMOVAL		SUBBASE GRAN. MAT., TYPE C	BIT. MAT. (PRIME COAT)	POLYMERIZED BIT. MAT. (PRIME COAT)		HMA SHOULDERS		SHOULDER RUMBLE STRIPS, 16 INCH		AGGREGATE SHOULDER REMOVAL	AGGREGATE SHOULDERS, TYPE B	
	LT	RT				LT	RT			GRAN. SUBBASE	COLD-MILLED	FOG COAT	LT	RT	LT			RT
	FT		SQ YD	SQ YD	SQ YD	SQ YD		TON	TON	TON		TON		FT		CU YD	TON	
I-155 SOUTHBOUND LANES																		
STA. 32+75.00 TO STA. 45+23.42	6.00	10.00				832.28	1,387.13	1,075.31	4.44		0.49	372.86	621.44	1,248.42	1,248.42	169.46	347.40	
STA. 45+23.42 TO STA. 46+11.42	6.00	10.00				58.67	97.78	75.80	0.31		0.03	26.28	43.80					
STA. 46+11.42 TO STA. 48+09.25									OMISSION S.N. 090-0128									
STA. 48+09.25 TO STA. 48+19.00	6.00	10.00	17.33							0.01		1.37	2.28					
STA. 48+19.00 TO STA. 48+97.25	6.00	10.00				52.17	86.94	67.40	0.28		0.03	23.37	38.95					
STA. 48+97.25 TO STA. 55+50.00	6.00	10.00				435.17	725.28	562.24	2.32		0.26	194.95	324.92	652.75	652.75	88.60	181.64	
STA. 55+50.00 TO STA. 56+00.00	6.00	10.00	55.56			33.33		20.27	0.07		0.02	14.93	12.44	50.00	50.00	2.47	10.54	
STA. 56+00.00 TO STA. 59+75.51	6.00	10.00	417.23			250.34		152.21	0.50		0.14	112.15	93.46	375.51	375.51	18.53	79.17	
STA. 59+75.51 TO STA. 60+76.95	6.00	10.00	180.34								0.06	14.20	23.67					
STA. 60+76.95 TO STA. 62+58.95									OMISSION S.N. 090-0128									
STA. 62+58.95 TO STA. 63+46.95	6.00	0.00				58.67		35.67	0.12		0.01	26.28						
STA. 63+46.95 TO STA. 66+16.56	6.00	0.00				179.74		109.27	0.36			80.52		269.61		13.31	47.75	
STA. 66+16.56 TO STA. 73+45.00	6.00	10.00				485.63	809.38	274.49	2.59		0.28	217.56	362.60	728.44	728.44	98.88	202.70	
STA. 73+45.00 TO STA. 76+50.00	6.00	10.00				203.33	338.89	232.71	1.08		0.12	91.09	151.82	305.00	305.00	41.40	84.87	
STA. 76+50.00 TO STA. 79+29.76	6.00	10.00	310.84			186.51		133.40	0.37		0.11	83.55	65.28	279.76	279.76	13.81	58.98	
STA. 79+29.76 TO STA. 90+79.76	6.00	0.00				766.67		466.83	1.53		0.17	343.47	0.00	1,150.00		56.75	203.66	
STA. 90+79.76 TO STA. 94+70.00	6.00	10.00	433.60			260.16		189.8	0.52		0.15	116.55	91.06	390.24	390.24	19.26	82.27	
STA. 94+70.00 TO STA. 96+78.18	6.00	10.00	138.79				231.31	94.3	0.46		0.05	29.15	103.63	208.18	208.18	10.27	33.35	
STA. 96+78.18 TO STA. 103+38.25	6.00	0.00	440.05								0.15	92.41		660.07			38.97	
STA. 103+38.25 TO STA. 111+23.08	6.00	10.00	1,395.25								0.47	109.88	183.13	784.83	784.83		72.80	
STA. 111+23.08 TO STA. 112+50.00	6.00	10.00			225.64						0.08	17.77	29.61	126.92	126.92		7.49	
STA. 112+50.00 TO STA. 116+12.25	6.00	10.00			241.50		402.50	161.19	0.81		0.22	50.72	180.32	362.25	362.25	17.88	58.03	
STA. 116+12.25 TO STA. 122+50.00	6.00	10.00	425.17				708.61	299.81	1.42		0.39	89.29	317.46	637.75	637.75		102.17	
STA. 122+50.00 TO STA. 145+10.00	6.00	10.00	2,511.11			1,506.67		919.05	3.01		0.85	674.99	527.33	2,260.00	2,260.00	111.54	476.46	
STA. 145+10.00 TO STA. 160+00.00	6.00	10.00	2,648.89								0.90	208.60	347.67	1,490.00	1,490.00		138.21	
STA. 160+00.00 TO STA. 163+50.00	6.00	10.00	388.89			233.33		141.7	0.47		0.13	104.53	81.67	350.00	350.00	17.27	73.79	
STA. 163+50.00 TO STA. 166+43.83	6.00	0.00				195.89		119.50	0.39		0.04	87.76	0.00	293.83		14.50	52.04	
STA. 166+43.83 TO STA. 167+06.37 BK	6.00	10.00	69.49			41.69		53.2	0.08		0.02	18.68	14.59	62.54	62.54	3.09	13.18	
STA. 164+34.54 AH TO STA. 170+15.00	6.00	10.00	644.96			386.97		235.28	0.77		0.22	173.36	135.44	580.46	580.46	28.65	122.37	
STA. 170+15.00 TO STA. 177+69.73	6.00	10.00	1,341.74								0.46	105.66	176.10	754.73	754.73		70.01	
STA. 177+69.73 TO STA. 185+00.00	6.00	0.00	486.85								0.17	102.24		730.27			67.74	
STA. 185+00.00 TO STA. 186+32.00	6.00	19.40	284.46			88.00		53.50	0.18		0.10	39.42	59.74	132.00	132.00	6.51	27.83	
STA. 186+32.00 TO STA. 188+93.29	6.00	13.40	388.89			174.19		105.9	0.35		0.13	78.04	81.67	281.29	281.29	12.90	55.09	
STA. 188+93.29 TO STA. 189+43.00	6.00	13.40			74.01	33.14		20.15	0.07		0.03	14.85	15.54	49.71	49.71	2.45	10.48	
STA. 189+43.00 TO STA. 193+78.46	6.00	10.00			483.84	290.31		176.51	0.58		0.16	130.06	101.61	435.46	435.46	21.49	91.80	
STA. 193+78.46 TO STA. 199+86.38	6.00	10.00	675.47			405.28		246.41	0.81		0.23	181.57	141.85	607.92	607.92	30.00	128.16	
STA. 199+86.38 TO STA. 205+70.00	6.00	0.00				389.08		236.56	0.78		0.00	174.31		583.62		28.80	103.36	
STA. 205+70.00 TO STA. 211+36.38	6.00	0.00	377.59								0.13	79.29		566.38			33.43	
STA. 211+36.38 TO STA. 218+00.00	6.00	10.00	1,179.77								0.40	92.91	154.84	663.62	663.62		61.55	
STA. 218+00.00 TO STA. 223+00.00	6.00	10.00				333.33	555.56	430.67	1.78		0.20	149.33	248.89	500.00	500.00	67.87	139.13	
STA. 223+00.00 TO STA. 228+00.00	6.00	10.00	555.56			333.33		202.67	0.67		0.19	149.33	116.67	500.00	500.00	24.68	105.41	
STA. 228+00.00 TO STA. 237+50.00	6.00	10.00	1,688.89								0.57	133.00	221.67	950.00	950.00		88.12	
STA. 237+50.00 TO STA. 242+50.00	6.00	10.00	555.56			333.33		202.67	0.67		0.19	149.33	116.67	500.00	500.00	24.68	105.41	
STA. 242+50.00 TO STA. 247+50.00	6.00	10.00				333.33	555.56	430.67	1.78		0.20	149.33	248.89	500.00	500.00	67.87	139.13	
STA. 247+50.00 TO STA. 252+50.00	6.00	10.00	555.56			333.33		202.67	0.67		0.19	149.33	116.67	500.00	500.00	24.68	105.41	
STA. 252+50.00 TO STA. 257+50.00	6.00	10.00				333.33	555.56	430.67	1.78		0.20	149.33	248.89	500.00	500.00	67.87	139.13	
STA. 257+50.00 TO STA. 271+50.00	6.00	10.00	1,555.56			933.33		567.47	1.87		0.53	418.13	326.67	1,400.00	1,400.00	69.09	295.15	
STA. 271+50.00 TO STA. 275+55.00	6.00	10.00				270.00	450.00	348.84	1.44		0.16	120.96	201.60	405.00	405.00	54.98	112.70	
STA. 275+55.00 TO STA. 279+60.00	6.00	10.00	450.00			270.00		164.16	0.54		0.15	120.96	94.50	405.00	405.00	19.99	85.38	
STA. 279+60.00 TO STA. 284+60.00	6.00	10.00				333.33	555.56	430.67	1.78		0.20	149.33	248.89	500.00	500.00	67.87	139.13	

REVISIED SHEET 2/22/12

DELETED

FILE NAME = D:\69914-1-155 Typicals.dgn

USER NAME = johnstvt
 PLOT SCALE = 1/8"=1'-0"
 PLOT DATE = 2/21/2012

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 8 OF 27 SHEETS STA. TO STA.

F.A.I. SECTION COUNTY TOTAL SHEETS SHEET NO.
 155 90108RS-4(107,106,106X)RS-2) TAZEWELL 92 31
 CONTRACT NO. 68914
 [ILLINOIS] FED. AID PROJECT