TABULATION OF SHOULDER QUANTITIES (CONTINUED)

LOCATION	WIDTH LT	WIDTH RT	HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 2"	HMA SURFACE REMOVAL, 3 3/4"	PAVED SHOULDER REMOVAL LT	PAVED SHOULDER REMOVAL RT	SUBBASE GRAN. MAT., TYPE C	BIT. MAT. (PRIME COAT) GRAN. SUBBASE	POLYMERIZED BIT. MAT. (PRIME COAT) COLD-MILLED	POLYMERIZED BIT. MAT. (PRIME COAT) FOG COAT	HMA SHOULDERS LT	HMA SHOULDERS RT	SHOULDER RUMBLE STRIPS, 16 INCH LT	SHOULDER RUMBLE STRIPS, 16 INCH RT	AGGREGATE SHOULDER REMOVAL	AGGREGATE SHOULDERS, TYPE B
	FT		SQ YD	SQ YD	SQ YD	SQ YD		TON	TON	TON		TON		FT		CU YD	TON
I-155 NORTHBOUND LANES																	
STA. 529+65.98 TO STA. 564+50.00	10.00	6.00	6,193.81							2.11	1.36	812.94	487.76	3,484.02	3,484.02		323.16
STA. 564+50.00 TO STA. 574+15.00	10.00	6.00	1,072.22				643.33	391.15	1.29	0.36	0.38	225.17	288.21	965.00	965.00	47.62	203.44
STA. 574+15.00 TO STA. 606+47.59 BK	10.00	6.00	5,746.83							1.95	1.26	754.27	452.56	3,232.59	3,232.59		299.84
STA. 608+08.87 AH TO STA. 611+43.78	10.00	6.00	595.40							0.20	0.13	78.15	46.89	334.91	334.91		31.06
STA. 611+43.78 TO STA. 615+96.95	10.00	6.00			805.64					0.27	0.18	105.74	63.44	453.17	453.17		42.03
NORTHBOUND LANES SUB-TOTAL:			**69,022.11**		**1,313.60**	**13,636.43**	**9,014.43**	**1,077.1**	**45.30**	**23.89**	**20.44**	**14,667.33**	**10,243.62**	**50,667.93**	**59,279.54**	**1,446.66**	**7,373.53**
BIRCHWOOD INTERCHANGE																	
RAMP A																	
STA. 00+00 TO STA. 0+23.12	0.00	6.00		15.41						0.01			3.67				1.36
STA. 0+23.12 TO STA. 1+11.12	0.00	6.00		58.67			58.67	35.6	0.12	0.00	0.01		26.28			4.34	
STA. 1+11.12 TO STA. 3+17.59									OMISSION S.N. 090-0129								
STA. 3+17.59 TO STA. 4+05.59	0.00	6.00															
STA. 4+05.59 TO STA. 6+64.73	0.00	6.00		172.76						0.06	0.04		41.12				15.30
STA. 6+64.73 TO STA. 22+09.85	4.00	6.00		1,716.80						0.58	0.38	163.44	245.16				182.42
STA. 22+09.85 TO STA. 22+75.92	0.00	0.00															
RAMP A SUB-TOTAL:				**1,963.64**			**58.67**	**35.67**	**0.12**	**0.65**	**0.43**	**163.44**	**316.23**			**4.34**	**199.09**
RAMP B																	
STA. 0+61.55 TO STA. 0+78.16	0.00	6.00		11.07									2.64				0.98
STA. 0+78.16 TO STA. 14+82.46	4.00	6.00		1,560.33						0.53	0.34	148.54	222.82				165.80
STA. 14+82.46 TO STA. 15+70.46	4.00	6.00															
STA. 15+70.46 TO STA. 17+45.19									OMISSION S.N. 090-0127								
STA. 17+45.19 TO STA. 18+33.19	4.00	6.00															
STA. 18+33.19 TO STA. 19+71.26	4.00	6.00		153.41						0.05	0.03	14.60	21.91				16.30
STA. 19+71.26 TO STA. 30+57.30	0.00	6.00		724.03						0.25	0.16		172.32				64.11
STA. 30+57.30 TO STA. 31+22.35	0.00	6.00		43.37						0.01	0.01		10.32				3.84
RAMP B SUB-TOTAL:				**2,492.21**						**0.84**	**0.55**	**163.15**	**430.00**				**251.03**
RAMP C																	
STA. 00+00 TO STA. 0+96.56	0.00	6.00		64.37						0.02			15.32				5.70
STA. 0+96.56 TO STA. 1+26.56	0.00	6.00		20.00						0.01	0.00		4.76				1.77
STA. 1+26.56 TO STA. 3+08.14									OMISSION S.N. 090-0128								
STA. 3+08.14 TO STA. 3+96.14	0.00	6.00															5.19
STA. 3+96.14 TO STA. 5+48.17	0.00	6.00		101.35						0.03	0.02		24.12				8.97
STA. 5+48.17 TO STA. 6+64.73	0.00	6.00					77.71	47.25	0.16		0.02		34.81			5.75	20.64
STA. 6+64.73 TO STA. 22+27.00	4.00	6.00		1,735.86						0.59	0.38	165.25	247.88				184.45
STA. 22+27.00 TO STA. 22+97.22	0.00	6.00		46.81						0.02	0.01		11.14				4.15
RAMP C SUB-TOTAL:				**1,968.40**			**77.71**	**47.25**	**0.16**	**0.67**	**0.44**	**165.25**	**338.04**			**5.75**	**230.88**
RAMP D																	
STA. 0+64.62 TO STA. 1+36.47	4.00	0.00		31.93						0.01		7.60					4.24
STA. 1+36.47 TO STA. 19+87.71	4.00	6.00		2,056.93						0.70	0.45	195.82	293.73				218.57
STA. 19+87.71 TO STA. 31+37.71	0.00	6.00		766.67						0.26	0.17		182.47				67.89
RAMP D SUB-TOTAL:				**2,855.53**				**0.00**		**0.97**	**0.62**	**203.42**	**476.20**				**290.70**

DELETED

△1 REVISED SHEET 2\22\12

FILE NAME = 0468914-I-155 Typicals.dgn	USER NAME = johnsontv	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A.I. RTE. 155	SECTION 90(108RS-4)(107,106,106)(RS-2)	COUNTY TAZEWELL	TOTAL SHEETS 92 / SHEET NO. 34
		DRAWN -	REVISED -					CONTRACT NO. 68914	
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -		NOT TO SCALE / SHEET NO. 11 OF 27 SHEETS / STA. TO STA.		ILLINOIS FED. AID PROJECT		
	PLOT DATE = 2/21/2012	DATE -	REVISED -						