

TABULATION OF RESURFACING QUANTITIES (CONTINUED)

LOCATION	PCC SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 1 1/2 IN	HMA SURFACE REMOVAL, 3 3/4 IN	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)			POLYMERIZED HMA SURFACE COURSE, MIX "E", N90	POLYMERIZED HMA SURFACE COURSE, MIX "D", N70	POLYMERIZED HMA BINDER COURSE, IL-12.5, N90	POLYMERIZED LEVELING BINDER (MM) IL-4.75, N50	HMA BASE CSE WIDENING 10 3/4 IN	HMA BASE CSE 10 3/4 IN
						COLD-MILLED	EXIST. PVMT.	FOG COAT						
						TON								
QUEENWOOD ROAD INTERCHANGE														
RAMP A														
STA. 00+00 TO STA. 6+60.07				1,365.24		0.46		0.30		114.68		57.34		
STA. 6+60.07 TO STA. 14+55.80				1,414.63		0.48		0.31		118.83		59.41		
STA. 14+55.80 TO STA. 16+50.73				1,032.91		0.35		0.23		86.76		43.38		
STA. 16+50.73 TO STA. 16+80.73		345.65	63.83			0.12				29.03				
RAMP A SUB-TOTAL:		345.65	63.83	3,812.79		1.41		0.84		349.31		160.14		
RAMP B														
STA. 0+26.50 TO STA. 0+56.50		338.90	56.48			0.12				28.47				
STA. 0+56.50 TO STA. 1+36.35				362.83		0.12		0.08		30.48		15.24		
STA. 1+36.35 TO STA. 9+14.40				1,383.20		0.47		0.30		116.19		58.09		
STA. 9+14.40 TO STA. 11+14.40				488.89		0.17		0.11		41.07		20.53		
STA. 11+14.40 TO STA. 20+64.40				1,108.33		0.38		0.24		93.10		46.55		
RAMP B SUB-TOTAL:		338.90	56.48	3,343.25		1.25		0.74		309.30		140.42		
MAIN STREET INTERCHANGE														
RAMP C														
STA. 7+40.31 TO STA. 7+70.31		93.52	15.59			0.03				7.86				
STA. 7+70.31 TO STA. 16+51.00				1,565.67		0.53		0.34		131.52		65.76		
STA. 16+51.00 TO STA. 16+81.00		53.33	8.89			0.02				4.48				
STA. 16+81.00 TO STA. 23+42.00														
STA. 23+42.00 TO STA. 23+72.00		53.33	8.89			0.02				4.48				
STA. 23+72.00 TO STA. 37+15.42				2,388.30		0.81		0.53		200.62		100.31		
STA. 37+15.42 TO STA. 41+15.42				711.11		0.24		0.16		59.73		29.87		
RAMP C SUB-TOTAL:		200.18	33.36	4,665.08		1.65		1.03		408.68		195.93		
RAMP D														
STA. 00+00 TO STA. 6+60.07				1,365.24		0.46		0.30		114.68		57.34		
STA. 6+60.07 TO STA. 23+43.90				2,993.48		1.02		0.66		251.45		125.73		
STA. 23+43.90 TO STA. 23+73.90		93.52	15.59			0.03				7.86				
RAMP D SUB-TOTAL:		93.52	15.59	4,358.72		1.51		0.96		373.99		183.07		

OMISSION S.N. 090-0131