

TABULATION OF RESURFACING QUANTITIES (CONTINUED)

LOCATION	PCC SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 1 1/2 IN	HMA SURFACE REMOVAL, 3 3/4 IN	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)			POLYMERIZED HMA SURFACE COURSE, MIX "E", N90	POLYMERIZED HMA SURFACE COURSE, MIX "D", N70	POLYMERIZED HMA BINDER COURSE, IL-12.5, N90	POLYMERIZED LEVELING BINDER (MM) IL-4.75, N50	HMA BASE CSE WIDENING 10 3/4 IN	HMA BASE CSE 10 3/4 IN	
						COLD-MILLED	EXIST. PVMT.	FOG COAT							
						TON									TON
SQ YD	SQ YD	SQ YD	SQ YD	SQ YD											
IL 9 INTERCHANGE															
RAMP A															
STA. 0+40.28 TO STA. 0+70.28		369.15	61.53			0.13				31.01					
STA. 0+70.28 TO STA. 1+48.96				343.66		0.12	0.08		28.87			14.43			
STA. 1+48.96 TO STA. 10+91.21				1,675.11		0.57	0.37		140.71			70.35			
STA. 10+91.21 TO STA. 12+91.21				488.89		0.17	0.11		41.07			20.53			
STA. 12+91.21 TO STA. 22+41.21				1,108.33		0.38	0.24		93.10			46.55			
RAMP A SUB-TOTAL:		369.15	61.53	3,615.99		1.35	0.80		334.75			151.87			
RAMP B															
STA. 00+00 TO STA. 6+57.13				1,359.16		0.46	0.30		114.17			57.08			
STA. 6+57.13 TO STA. 15+59.61				1,604.41		0.55	0.35		134.77			67.39			
STA. 15+59.61 TO STA. 16+71.89				522.16		0.18	0.11		43.86			21.93			
STA. 16+71.89 TO STA. 17+01.89		326.17	59.08			0.11			27.40						
RAMP B SUB-TOTAL:		326.17	59.08	3,485.74		1.30	0.77		320.20			146.40			
RAMP C															
STA. 0+40.50 TO STA. 0+70.50		373.52	62.25			0.13			31.38						
STA. 0+70.50 TO STA. 1+48.96				346.66		0.12	0.08		29.12			14.56			
STA. 1+48.96 TO STA. 10+76.19				1,648.41		0.56	0.36		138.47			69.23			
STA. 10+76.19 TO STA. 12+76.19				488.89		0.17	0.11		41.07			20.53			
STA. 12+76.19 TO STA. 22+28.53				1,111.06		0.38	0.24		93.33			46.66			
RAMP C SUB-TOTAL:		373.52	62.25	3,595.02		1.35	0.79		333.36			150.99			
RAMP D															
STA. 00+00 TO STA. 6+60.08				1,365.27		0.46	0.30		114.68			57.34			
STA. 6+60.08 TO STA. 15+83.00				1,640.75		0.56	0.36		137.82			68.91			
STA. 15+83.00 TO STA. 16+33.65				225.81		0.08	0.05		18.97			9.48			
STA. 16+33.65 TO STA. 16+63.65		323.26	59.51			0.11			27.15						
RAMP D SUB-TOTAL:		323.26	59.51	3,231.83		1.21	0.71		298.63			135.74			