

PAVEMENT MARKING SCHEDULE (CONTINUED)

LOCATION	PREFORMED PLASTIC PVMT MARKING, TY B		URETHANE PAVEMENT MARKING,						RAISED REFLECTIVE PAVEMENT MARKER				
	LINE 6"		LINE 4"		LINE 8"		LINE 12"	LINE 24"	LINE 18"	ONE-WAY CRYSTAL 80' O.C.	ONE-WAY CRYSTAL 40' O.C.	ONE-WAY CRYSTAL 20' O.C.	ONE-WAY AMBER 40' O.C.
	SKIP DASH WHITE		SOLID WHITE	SOLID YELLOW	SKIP DASH WHITE	SOLID WHITE	SOLID WHITE	SOLID WHITE	SOLID WHITE				
	FT		FT		FT	FT	FT	FT	FT	EACH			
BROADWAY INTERCHANGE													
RAMP A													
STA. 0+27.71	TO STA. 1+50		122	122		214	184						
STA. 1+50	TO STA. 8+41		691	691									
STA. 8+41	TO STA. 13+47		506			506				14			
STA. 13+47	TO STA. 20+90.55		744										
RAMP B													
STA. 0+00	TO STA. 3+00		300								16		
STA. 3+00	TO STA. 6+69		369			369				10	18		
STA. 6+69	TO STA. 18+50		1,181	1,181								9	
STA. 18+50	TO STA. 19+10.86		61	61		161	52	40					
RAMP C													
STA. 0+27.90	TO STA. 1+50		122	122		177	176						
STA. 1+50	TO STA. 8+55		705	705									
STA. 8+55	TO STA. 13+35		480			480				13			
STA. 13+35	TO STA. 20+90.55		756										
RAMP D													
STA. 0+00	TO STA. 4+80		480			480				13	25		
STA. 4+80	TO STA. 12+22		742	742								6	
STA. 12+22	TO STA. 14+18.07		196	196		342	135	40					
IL 9 INTERCHANGE													
RAMP A													
STA. 0+40.28	TO STA. 1+50		110	110		114	106						
STA. 1+50	TO STA. 10+89		939	939									
STA. 10+89	TO STA. 14+73		384			384				11			
STA. 14+73	TO STA. 22+41.21		768										
RAMP B													
STA. 0+00	TO STA. 2+64		264								14		
STA. 2+64	TO STA. 6+73		409			409				11	20		
STA. 6+73	TO STA. 16+00		927	927								9	
STA. 16+00	TO STA. 16+60.74		61	61		134	49	40					
RAMP C													
STA. 0+40.50	TO STA. 1+50		110	110		152	114						
STA. 1+50	TO STA. 10+99		949	949									
STA. 10+99	TO STA. 13+89		290			290				8			
STA. 13+89	TO STA. 22+28.53		840										
RAMP D													
STA. 0+00	TO STA. 2+88		288								15		
STA. 2+88	TO STA. 6+68		380			380				11	19		
STA. 6+68	TO STA. 15+50		882	882								13	
STA. 15+50	TO STA. 16+99.90		150	150		136	86	40					

FILE NAME = D468914-1-155 Typo001.dgn

USER NAME = johnsonv

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.0000' / 1"

CHECKED -

REVISED -

PLOT DATE = 1/9/2012

DATE -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 17 OF 27 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	90108RS-4(107,106,106XRS-2)	TAZEWELL	92	40
68914			CONTRACT NO. 68914	
ILLINOIS FED. AID PROJECT				