

SCHEDULE OF EARTHWORK QUANTITIES

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	TOPSOIL FURNISH & PLACE, 4"
	CU YD	CU YD	CU YD	CU YD	SQ YD
BROADWAY INTERCHANGE RAMP D					
STA. 10+00 TO STA. 10+50	11.6	8.7	1.1	+7.6	119.44
STA. 10+50 TO STA. 11+00	23.0	17.25	21.5	-4.3	248.20
STA. 11+00 TO STA. 11+50	19.6	14.7	67.4	-52.7	259.92
STA. 11+50 TO STA. 12+00	15.9	11.925	124.5	-112.6	266.98
STA. 12+00 TO STA. 12+50	14.8	11.1	174.3	-163.2	277.17
STA. 12+50 TO STA. 13+00	11.9	8.925	188.9	-180.0	288.64
STA. 13+00 TO STA. 13+50	16.6	12.45	165.4	-153.0	320.20
STA. 13+50 TO STA. 14+00	11.8	8.85	73.4	-64.6	172.92
SUB-TOTAL	125.2	93.9	816.5	-722.6	1,953.48
TOTAL	126	94	817	-723	1,954

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
I-155	9
TOTAL	9

CONSTRUCTING TEST STRIP	
LOCATION	EACH
I-155 MAINLINE	
HMA N90 SURFACE CSE	1
HMA N90 BINDER CSE	1
TOTAL	2

STONE DUMPED RIPRAP, CLASS A4	
LOCATION	SQ YD
I-155 MAINLINE	
SB STA. 77+40 TO STA. 88+25	1,446.67
NB STA. 180+08	40
NB STA. 529+00	225
SUB-TOTAL	
TOTAL	1,712

MOWING	
LOCATION	UNIT
I-155	3057
TOTAL	3,057

MATERIAL TRANSFER DEVICE	
LOCATION	TON
POLYMERIZED HMA SURFACE CSE	33,023
POLYMERIZED HMA BINDER CSE	38,230
POLYMERIZED LEVELING BINDER	3,629
TOTAL	74,882

MOBILIZATION	
LOCATION	L SUM
I-155	1
TOTAL	1

CONSTRUCTION LAYOUT	
LOCATION	L SUM
I-155	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION				
LOCATION	STD. 701401	STD. 701406	STD. 701411	STD. 701451
	L SUM	L SUM	EACH	L SUM
I-155 MAIN LINE AND RAMPS	1	1	20	1
TOTAL	1	1	20	1

FRAMES AND GRATES TO BE ADJUSTED	
LOCATION	EACH
I-155 MAINLINE	
NB STA. 62+69.50	2
TOTAL	2

FILE NAME = D:\68914-1-155 Typical.dgn

USER NAME = johnsonv

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.0000' / 1in.

CHECKED -

REVISED -

PLOT DATE = 1/9/2012

DATE -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

NOT TO SCALE SHEET NO. 21 OF 27 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
155	90108RS-4(107,106,106XRS-2)	TAZEWELL	92	44
68914			CONTRACT NO. 68914	
ILLINOIS FED. AID PROJECT				