

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
			90% FEDERAL	10% STATE 0021
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4773	
50104400	CONCRETE HEADWALL REMOVAL	EACH	174	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	24	
54246405	INLET BOX, STANDARD 542531	EACH	25	
54248510	CONCRETE COLLAR	CU YD	21	
542A0223	PIPE CULVERTS, CLASS A, TYPE 118"	FOOT	76	
550A0090	STORM SEWERS, CLASS A, TYPE 118"	FOOT	782	
550A0120	STORM SEWERS, CLASS A, TYPE 124"	FOOT	125	
550A0140	STORM SEWERS, CLASS A, TYPE 130"	FOOT	9	
550A0160	STORM SEWERS, CLASS A, TYPE 136"	FOOT	12	
55100900	STORM SEWER REMOVAL 18"	FOOT	85	
55101200	STORM SEWER REMOVAL 24"	FOOT	114	

FILE NAME = c:\pwwork\pwwork\keysrb\d0272688\057056-sht-500.dgn	USER NAME = keysrb	DESIGNED -	REVISED -
PLOT SCALE = 40.000' / in.	CHECKED -	REVISIED -	REVISIED -
PLOT DATE = 11/1/2011	DATE -	REVISIED -	REVISIED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	HSIP FY2012-1	CHAMPAIGN	160	3A
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 70956	