

70962

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	LOCATION OF WORK:		
				DOUGLAS COUNTY RURAL 90% STATE 10% CITY 0021	MCLEAN COUNTY URBAN 90% STATE 10% CITY 0021	MCLEAN COUNTY URBAN 90% STATE 10% CITY 0021
				CONSTRUCTION TYPE CODE:		
				QUANTITY	QUANTITY	QUANTITY
67100100	MOBILIZATION	L SUM	1.0	0.4	0.3	0.3
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.7		0.3
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2.0			2.0
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	25.0	1.0	22.0	2.0
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	8.0	6.0		2.0
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	9.0	3.0		6.0
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2.0			2.0
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1.0	1.0		
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2.0	2.0		
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	16.0	16.0		
X8803040	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	5.0	5.0		
X8803051	SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	1.0	1.0		
X8803082	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	6.0	6.0		
X8803084	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	17.0	17.0		
X8803088	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	11.0	11.0		
X8803090	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	1.0	1.0		
X8803910	SIGNAL HEAD ,LED, 2-FACE, 5-SECTION, BRACKET MOUNTED, RETROFIT	EACH	3.0	3.0		
X8950105	REMOVE EXISTING TRAFFIC CONTROLLER AND CABINET	EACH	2.0	2.0		
X8950305	REMOVE EXISTING SIGNAL HEAD	EACH	24.0	14.0		10.0
X8950307	REMOVE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	16.0	16.0		
X8803210	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, BRACKET MOUNTED, RETROFIT	EACH	1.0	1.0		

FILE NAME =	USER NAME = biggsrd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
et\pwork\puidot\biggsrd\0289275\sign	ls.dgn	DRAWN -	REVISED -					VAR.	*	**	11	6			
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -					CONTRACT NO. 70962							
	PLOT DATE = 12/16/2011	DATE -	REVISED -					ILLINOIS FED. AID PROJECT							

* LED RETROFIT AND UPS 2012-1
** MCLEAN, DOUGLAS