

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE							
				ROADWAY	PARKING LANES				SIDEWALK		
				80% FEDERAL 20% STATE	50% STATE / 50% VILLAGE 11' -6" TO 23' -6"		100% VILLAGE 23' -6"+		100% STATE	100% VILLAGE OF MODESTO	80% STATE 20% VILLAGE OF MODESTO
					MODESTO	PALMYRA	MODESTO	PALMYRA			
0005					0021						
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	3557	3557							
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	237	237							
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	60	60							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3873	3873							
50104400	CONCRETE HEADWALL REMOVAL	EACH	16	16							
50105220	PIPE CULVERT REMOVAL	FOOT	424	424							
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	130	130							
542D5470	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	601	601							
60238800	INLETS, TYPE A	EACH	2	2							
60404600	FRAMES AND GRATES, TYPE 9	EACH	2	2							
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	17.5	17.5							
60602500	CONCRETE GUTTER, TYPE A	FOOT	20	20							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8							
67100100	MOBILIZATION	L SUM	1	1							

FILE NAME =	USER NAME = mar.turk	DESIGNED -	REVISED 01/31/2012	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cf:\pwwork\pwwork\mar.turk\0264327\0672E48-sh1-500.dgn	PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -						608	120RS-2 & 121 RS-4	MACOUPIN	69	5
PLOT DATE = Jan-31-2012 10:05:00AM	DATE -	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72E48		
											ILLINOIS FED. AID PROJECT		