

BITUMINOUS MATERIALS (PRIME COAT)				
LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	QUANTITY (TON)
STA 561+72 TO 562+22	50	40.6	226	0.1

PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT			
LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	QUANTITY (SQ YD)
STA 561+72 TO 562+22	50	40.6	226

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70				
LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	QUANTITY (TON)
STA 561+72 TO 562+22	50	40.6	226	28

MOBILIZATION	
LOCATION	L SUM
JOB SITE	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	
LOCATION	L SUM
US 67 FOR EXIT TO IL 104 EAST	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	
LOCATION	L SUM
US 67	1

INLETS TO BE RECONSTRUCTED (SPECIAL)	
LOCATION	EACH
LT & RT STA 562+06	2

URETHANE PAVEMENT MARKING - LINE 5"	
LOCATION	FOOT
LT STA 561+72 TO 562+22 - OUTSIDE EOP - YELLOW	50
LT STA 561+72 TO 562+22 - SKIP DASH - WHITE	20
LT STA 561+72 TO 562+22 - INSIDE EOP - WHITE	50
TOTAL	120

SILICONE JOINT SEALER, 3"	
LOCATION	FOOT
STA 561+92	40

POLYMER CONCRETE				
LOCATION	LENGTH (FOOT)	WIDTH (IN)	AVERAGE DEPTH (IN)	QUANTITY (CU FT)
STA 561+92	40	7.0	2.50	4.9