

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED 20% STATE 0011			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	14	14			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5			
40600300	AGGREGATE (PRIME COAT)	TON	3	3			
40600990	TEMPORARY RAMP	SQ YD	54	54			
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	93	93			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	48	48			
44000100	PAVEMENT REMOVAL	SQ YD	269	269			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1527	1527			
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	674	674			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	35	35			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1			
50105220	PIPE CULVERT REMOVAL	FOOT	18	18			
50300225	CONCRETE STRUCTURES	CU YD	22.8	22.8			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	112	112			

FILE NAME = #FILEL#	USER NAME = Paul	DESIGNED - JLS	REVISED -
		DRAWN - PDB	REVISED -
	PLOT SCALE = 48,0000' / IN.	CHECKED - BRM	REVISED -
	PLOT DATE = 12/8/2011	DATE - 02-08-11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	20BR	CLINTON	51	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76B43	