

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80%_FED 20%_STATE 0005				CODE NO	ITEM		UNIT	80%_FED 20%_STATE 0005	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	80	80			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	537	537			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11274	11274		* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	3	3			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	406	406		* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	50475	50475		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	537	537			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	80	80		80300100	LOCATING UNDERGROUND CABLE	FOOT	100	100			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	175	175		88600600	DETECTOR LOOP REPLACEMENT	FOOT	2346	2346			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16826	16826		+ 20076600	TRAINEES	HOUR	500	500			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	406	406									
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50475	50475									

*SPECIALTY ITEM +0042

FILE NAME =	USER NAME = milleraj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwork\pudot\milleraj\0260814\d87	2e96-sht-plan.dgn	DRAWN -	REVISED -			582	6-3, 6-1RS-3	MADISON	66	4	
	PLOT SCALE = 100.0000' / 1 in.	CHECKED -	REVISED -			CONTRACT NO. 76E96					
	PLOT DATE = 12/16/2011	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					