DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE ROADWAY 0004	100% CITY CITY 0021	80% FED 20% STATE TRAINEES 0042	80% FED 20% STATE BRIDGE 0011
54248510	CONCRETE COLLAR	CU YD	5.6	5.6			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	400	400			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	2,063	2,063			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	209	209			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	671	671			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	327	327			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	250	250			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1,482	1,482			
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	122	122			
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	481	481			
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	233	233			
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	265	265			
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	235	235			
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	250	250			
55100500	STORM SEWER REMOVAL 12"	FOOT	40	40			
55100700	STORM SEWER REMOVAL 15"	FOOT	647	647			
55100900	STORM SEWER REMOVAL 18"	FOOT	263	263			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	81.0				81.0
60100915	PIPE DRAINS 6"	FOOT	50	50			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	5	5			
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	7	7			
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	6	6			
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	18	18			
60223810	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2	2			
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	4	4			
60235300	INLETS, TYPE A, TYPE 1 FRAME CLOSED LID	EACH	1	1			
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	19	19			
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	15	15			
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	32	32			
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	2			
60260100	INLETS TO BE ADJUSTED	EACH	2	2			
60500040	REMOVING MANHOLES	EACH	3	3			
60500060	REMOVING INLETS	EACH	4	4			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10,543	10,543			
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	47	47			
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	65	65			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	398	398			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	850	850			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	4,690	4,690			
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	75	75			
63301210	REMOVE AND RE-ERECT STEEL BEAM GUARD RAIL, TYPE A	FOOT	223	223			
63500105	DELINEATORS	EACH	17	17			
66500105	WOVEN WIRE FENCE 4'	FOOT	420	420			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	144	144			
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	41	41			
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4	4			

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE ROADWAY 0004	100% CITY CITY 0021	80% FED 20% STATE TRAINEES 0042	80% FED 20% STATE BRIDGE 0011
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24			
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	24	24			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.67			0.33
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	30	30			
X 70106210	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	EACH	1	1			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	3	3			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,776	7,776			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123.6	123.6			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	461,638	461,638			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,836	1,836			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	618	618			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4,404	4,404			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,389	1,389			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16,029	16,029			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,337.5	1,337.5			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,337.5	1,337.5			
70500500	TEMPORARY STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	12	12			
* 72000100	SIGN PANEL - TYPE 1	SQ FT	90	90			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	150	150			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	282	282			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	162	162			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	136,197	136,197			
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	90	90			
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123.6	123.6			
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	12,774	12,774			
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	330	330			
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	206	206			
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	1,468	1,468			
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	135	135			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	937	937			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16			
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	*	JASPER	545	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(5,6)Y,RS-2,6BR-7
CONTRACT NO. 94437

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP ROUTE 95 (IL RTE. 33)
SECTION (5,6)Y,RS-2,6BR-7
JASPER COUNTY

SCALE: VERT.
HORIZ.
DATE: 09/16/02

DRAWN BY: BISHOP
DESIGNED BY: COLBROOK
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
3500 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-0079
PROFESSIONAL DESIGN FIRM NO. 184-000579 CORPORATION
(217) 793-3696, (217) 793-3227 FILE MAIL oodesignsoonofficeofficefirm.com

COMPUTER FILE NO.
SUMMARY - 50

PROJECT 01256
4/21/11 - AH

*SPECIALTY ITEM ⚠ REVISED 2/22/12