

TEMPORARY CONCRETE BARRIER WALL

STATION / LOCATION		TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TL2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TL2	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TL2	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TL2	MODULAR GLARE SCREEN SYSTEM	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	
STATION	TO	STATION	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)	(EACH)
STAGE 1B										
IL 13										
1725+00.00	-	1738+00.00	1,092		1	3			937	21
1738+00.00	-	1751+00.00	2,680			4			1,167	39
1751+00.00	-	1764+00.00	2,436			2			1,131	37
1764+00.00	-	1755+00.00	1,118						626	19
STAGE 1B SUBTOTALS			7,326	0	1	9	0	0	3,861	116
STAGE 2A										
IL 13										
1725+00.00	-	1738+00.00		790			1	1	598	
1738+00.00	-	1751+00.00		2,211				1	1,247	
1751+00.00	-	1764+00.00		2,102				3	1,148	
1764+00.00	-	1755+00.00		572				1	572	
STAGE 2A SUBTOTALS			0	5,675	0	0	1	6	3,565	0
TOTALS			7,326	5,675	1	9	1	6	7,426	116

TEMPORARY PAVING

STATION / LOCATION		PAVEMENT REMOVAL	HMA PAVEMENT (FULL DEPTH) 10"	SUBBASE GRANULAR MATERIAL, TYPE B 4"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TEMPORARY RAMPS	BITUMINOUS MATERIALS (PRIME COAT)	
STATION	TO	STATION	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(GAL)
STAGE 1A								
IL 13								
1725+00.00	-	1738+00.00	2,062	2,062	2,414	1,154.7		824.8
1738+00.00	-	1751+00.00	4,202	4,121	4,470	2,316.8		1,648.4
1751+00.00	-	1764+00.00	2,356	2,356	2,755	1,319.4		942.4
1764+00.00	-	1775+00.00	872	872	1,004	488.3		348.8
STAGE 1B								
IL 13								
1725+00.00	-	1738+00.00	172	172	213	96.3		68.8
1738+00.00	-	1751+00.00	208	11	19	28.2		4.4
1751+00.00	-	1764+00.00	45			5.0		
STAGE 1C								
IL 13								
1725+00.00	-	1738+00.00	142	142	168	79.5	1,142	56.8
STAGE 1D								
SKYLINE DR. (SOUTH)								
							93	
STAGE 1F								
IL 13								
1725+00.00	-	1738+00.00	349	349	447	195.4		139.6
1764+00.00	-	1775+00.00	421	421	519	235.8		168.4
STAGE 2A								
IL 13								
1751+00.00	-	1764+00.00	104	104	119	58.2		41.6
STAGE 2C								
SKYLINE DR. (NORTH)								
12+73.17	-	13+13.17					54	
STAGE 2D								
SKYLINE DR. (NORTH)								
12+73.17	-	14+15.00					141	
STAGE 2E								
IL 13								
1725+00.00	-	1738+00.00	92	92	107	51.5		36.8
TOTALS			11,025	10,702	12,235	6,029.1	1,430	4,280.8

1 REVISIED
2/24/12

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
I:\dot\0906083\draw\cadd\sheet\099885	OpenH86 Springfield	MJO	
	Plot-Schedules.Add.dgn	DRAWN -	REVISED -
		MJO	
	PLOT SCALE = 50.0000 / IN.	CHECKED -	REVISED -
		BMB	
	PLOT DATE = 2/23/2012	DATE -	REVISED -
		12/9/11	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1X-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	48
CONTRACT NO. 98859			ILLINOIS FED. AID PROJECT	