

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR. BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0008 0040	0021
50300300	PROTECTIVE COAT	SQ YD	9,764		5,084	2,162	2,518	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.8	0.2		
50500505	STUD SHEAR CONNECTORS	EACH	22,362		16,944	5,418		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	988,610		644,780	202,160	141,670	
50800515	BAR SPLICERS	EACH	444		228	216		
50800530	MECHANICAL SPLICERS	EACH	400		400			
51100100	SLOPE WALL 4 INCH	SQ YD	2,559		2,559			
51201600	FURNISHING STEEL PILES HP12X53	FOOT	5,203		2,280	2,923		
51202305	DRIVING PILES	FOOT	5,203		2,280	2,923		
51203600	TEST PILE STEEL HP12X53	EACH	6		4	2		
51204650	PILE SHOES	EACH	44		44			
51500100	NAME PLATES	EACH	4		2	2		
X 51603000	DRILLED SHAFT IN SOIL	CU YD	596.4		596.4			
X 51604000	DRILLED SHAFT IN ROCK	CU YD	58.8		58.8			

X SPECIALTY ITEM

FILE NAME =	USER NAME = Matt Overbey	DESIGNED -	REVISED -
I:\dot\0906603\draw\cadd\sheet\0998859.sht-S03001.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 13

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	9
SCALE: N/A			SHEET NO. OF SHEETS STA. N/A TO STA. N/A	
ILLINOIS FED. AID PROJECT CONTRACT NO. 98859				