

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0040 0008	0021
52000110	PREFORMED JOINT STRIP SEAL	FOOT	224			224		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14			14		
52100510	ANCHOR BOLTS, 3/4"	EACH	28			28		
52100520	ANCHOR BOLTS, 1"	EACH	64		64			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	92		64	28		
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	88	88				
542A1099	PIPE CULVERTS, CLASS A, TYPE 2 54"	FOOT	21	21				
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	78	78				
5421A015	PIPE CULVERTS, CLASS A, TYPE 1 15" (TEMPORARY)	FOOT	275	275				
5421A042	PIPE CULVERTS, CLASS A, TYPE 1 42" (TEMPORARY)	FOOT	20	20				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2				

FILE NAME =	USER NAME = Matt Overbey	DESIGNED -	REVISED -
1:\dot\990603\draw\cadd_sheets\0998859\shh-500801.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
ILLINOIS ROUTE 13			
SCALE: N/A	SHEET NO.	OF SHEETS	STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1X-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	10
CONTRACT NO. 98859			ILLINOIS FED. AID PROJECT	