

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0008	0021
81300560	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 18" 16"	EACH	4					4
81400100	HANDHOLE	EACH	15					15
81500100	GULFBOX JUNCTION	EACH	4					4
X 81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TY. USE), 3/4" DIA. POLY.	FOOT	1,034					1,034
X 81603010	UNIT DUCT, 600V, 2-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TY. USE), 3/4" DIA. POLY.	FOOT	1,200					1,200
X 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	4,521					4,521
X 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	29					29
X 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8					8
X 82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	3					3
X 83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT	EACH	18					18
X 83062735	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT - TWIN	EACH	1					1
X 83600357	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	19					19
X 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	68					68
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	10					10

X SPECIALTY ITEM

FILE NAME =	USER NAME = Matt Dvorbey	DESIGNED -	REVISED -
I:\victor\090603\draw\cadd\sheet\099885	sh: 500081.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
ILLINOIS ROUTE 13				
SCALE: N/A	SHEET NO.	OF SHEETS	STA. N/A	TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	19
CONTRACT NO. 98859			ILLINOIS FED. AID PROJECT	